

Arenac County Remonumentation

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                       |             |               |
|---------------------------------------|-------------|---------------|
| <u>Arenac</u><br>(County)             | Located in: | Corner Code # |
| 1. Public Land Survey                 | T18N R 4E   | F-9           |
|                                       | T R         |               |
|                                       | T R         |               |
|                                       | T R         |               |
| 2. Property Controlling<br>in Section | S T R       |               |
|                                       | S T R       |               |
| 3. Miscellaneous<br>Property in Sec.  | S T R       |               |
|                                       | S T R       |               |

LIBER 002 PAGE 093

RECORDED  
JAN 2 11 15 AM '97  
ARENAC COUNTY  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael J. MacDonald, in a field survey on October 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |    |   |   |   |    |   |    |   |    |   |   |    |
|----|----|----|---|---|---|----|---|----|---|----|---|---|----|
| 1  | A  | B  | C | D | E | F  | G | H  | I | J  | K | L | M  |
| 2  | 6  | 5  |   |   |   | 4  |   | 3  |   | 2  |   |   | 1  |
| 3  |    |    |   |   |   |    |   |    |   |    |   |   |    |
| 4  | 7  | 8  |   |   |   | 9  |   | 10 |   | 11 |   |   | 12 |
| 5  |    |    |   |   |   |    |   |    |   |    |   |   |    |
| 6  | 18 | 17 |   |   |   | 16 |   | 15 |   | 14 |   |   | 13 |
| 7  |    |    |   |   |   |    |   |    |   |    |   |   |    |
| 8  | 19 | 20 |   |   |   | 21 |   | 22 |   | 23 |   |   | 24 |
| 9  |    |    |   |   |   |    |   |    |   |    |   |   |    |
| 10 | 30 | 29 |   |   |   | 28 |   | 27 |   | 26 |   |   | 25 |
| 11 |    |    |   |   |   |    |   |    |   |    |   |   |    |
| 12 | 31 | 32 |   |   |   | 33 |   | 34 |   | 35 |   |   | 36 |
| 13 |    |    |   |   |   |    |   |    |   |    |   |   |    |

A. Description of original monument and accessories and/or subsequent restoration:

F-9 Post set by J. Burt in 1843.  
MDOT Witness Card - L. 1, P. 206 set 1 1/4" well point (1964).



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 Fnd 1 1/4" well point 36" long on line between E-9 and G-9.  
Meas 2628.55' to G-9 (2628.54' - MDOT).  
Calc 2628.81' to E-9 (2628.53' - MDOT).  
Rec S 55° W 12.20' to 21" Maple; Meas S 50° W 12.55' to nail and tag  
in root on N side of 36" Maple.

Monument accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 Replaced well point with 5/8" x 24" long rebar with Arenac County Remonumentation cap.

S 50° W 12.55' to nail and tag in root on N side of 36" Maple.  
N 60° E 68.45' to nail and tag in SE face of 48" Maple.  
N 05° W 70.20' to nail and tag in E face of 24" Oak.  
S 05° W 52.90' to nail and tag in E face of 24" Maple.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 25 NOV. 1996  
Paul M. Glosek  
PAUL M. GLOSEK P.S., CHAIRMAN

Signed by Michael J. MacDonald Date 19 Dec 96  
Surveyor's Michigan License No. 22438