

SURVEY & REMONUMENTATION

MAR 05 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

ARENAC
(County)

Located In:

Corner Code # Page 1 of 1
ROSE SMITH

LC 2 / 143
1P

1. Public Land Survey

T18N. R 4E

G-5

ARENAC CO. REG. OF DEEDS
RS Rec. Date 12/23/97 Time 11:46
RECORDING FEES: 9.00

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, MICHAEL J. MACDONALD, in a field survey on SEPTEMBER 15, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT 'A' MEETING HELD ON 10/30/97

Paul M. Ciosek
PAUL M. CIOSEK P.S., CHAIRMAN

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-5

1. POST SET J. BURT D.S. IN 1843
W. PINE 25° S 1° E 50 LINKS
MAPLE 12° N 48° W 31 LINKS
2. EDMANDS SURVEY 1966, UNRECORDED, JOB #4319, NO CALL
3. EDMANDS SURVEY 1968, UNRECORDED, JOB #5313, NO CALL, DISTANCE TO G-4 2635.02' M, 2635.36' R.
4. EDMANDS SURVEY 1970, UNRECORDED, JOB #6606, NO CALL, DISTANCE TO H-5 2827.10' M., 2627.56' R.
5. SURVEY, L 1, P 8, (10/71) DE LA MATER; SW 48.85' TO TP, NE 39.9' TO 16" MAPLE, NW 44.25' TO 16" MAPLE
6. SURVEY, L 1, P 69, (3/73) MCGINNIS, FOUND 1/2" REROD
7. SURVEY, L 1, P 164 (9/74) RADCLIFFE, FOUND 1/2" IRON; N 45° W, 44.11', 24" MAPLE; N 45° E, 39.84', 30" MAPLE; S 45° E, 39.12', 23" MAPLE;
LCRC, L. 1, P.77, (10/6/73) RADCLIFFE, FOUND 1/2" IRON; N 45° W, 44.11', 24" MAPLE; N 45° E, 39.84', 30" MAPLE; S 45° E, 39.12', 23" MAPLE;
8. SURVEY, L 1, P 296 (8/12/76) GOSS, FND IRON; SW 48.7' TO TP, NW 43.3' TO 16" MAPLE, SE 38.75' TO 16" MAPLE
9. SURVEY, L 2, P 47 (9/93) RUDELL, FND 1/2" IRON
LCRC L 1, P 330 (9/2/93) RUDELL, FND 1/2" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5

SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND 1/2" REROD AS MENTIONED IN THE ABOVE MENTIONED LIBER AND PAGES. MONUMENT ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION TO THE ORIGINAL CORNER.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5

REPLACED FOUND 1/2" REROD WITH 5/8" x 24" LONG REROD WITH ARENAC CO. REMONUMENTATION CAP WITH 1/8" DRILL HOLE.
N 40° E 39.95' (39.95' R) FOUND N/T NW FACE 30" MAPLE
S 75° E 67.48' (67.52' R.) FOUND N/T N. FACE 28" MAPLE
S 40° W 54.87' TOP CENTER HYDRANT
S 65° W 49.09' (49.05' R.) FOUND N/T NW FACE CUTOFF UTILITY POLE
ON PHYSICAL CENTERLINE OF ROAD EAST & WEST (DUPRIE ROAD) AND 3' WEST TO PHYSICAL CENTERLINE NORTH & SOUTH ROAD (DEEP RIVER ROAD)
N 45° W 43.86' (43.85' R.) FOUND N/T S FACE 30" MAPLE

Signed by Michael J. MacDonald
Surveyor's Michigan License No. _____

Date 10 Dec 97



FIELD BOOK 2, PAGE 45