

APR 06 1999

ARENAC COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

ARENAC (County)

Located In:

Corner Code

Page 1 of 1 ROSE SMITH

LC 2/ 172 1P

ARENAC CO. REG. OF DEEDS

RS Rec. Date 12/29/98 Time 1:51 RECORDING FEES: 9.00

- 1. Public Land Survey T 18N R 4E G-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, DALE L. WINIECKE, in a field survey on JULY 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-6
1. ORIGINAL POST SET IN JULY 1843 BY J. BURT, D.S. WHITE PINE 22" S 53°W 5 LINKS WHITE PINE 18" S 77°E 15 LINKS
2. COUNTY SURVEYOR NOTES, FIELDBOOK 4, PAGE 38
3. CERTIFICATE OF SURVEY, L. 1, P. 164, J. RADCLIFFE, PS#11368, (1973), FOUND 3/8" IRON
4. LCRC - L. 1, P. 77, J. RADCLIFFE, PS#11368, (1973), FOUND 3/8" IRON
5. CERTIFICATE OF SURVEY, L. 1, P. 177, L. MCGINNIS, PS#18999, (1974), FOUND 3/8" IRON
6. LCRC - L. 1, P. 331, W. RUDELL, PS#14769, (1993), SET RR SPIKE USING G-5 AND 1/8 CORNER SET BY RADCLIFFE, L.1,P. 77
7. CERTIFICATE OF SURVEY, L.2, P.49-51, W. RUDELL PS#14769, (1993), SET RAILROAD SPIKE
8. CERTIFICATE OF SURVEY, L.2, P.47-8, W. RUDELL PS#14769, (1993), FOUND RAILROAD SPIKE
9. CERTIFICATE OF SURVEY - L. 2, P. 60-61, BY W. RUDELL, PS#14769, (1993), FOUND RR SPIKE, PER L. 1, P. 331

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND A 3/8"x 6" REROD 0.35' BELOW THE GRAVEL ROAD SURFACE. EXCAVATED THE AREA UNDER THE REROD AND FOUND NO OTHER OBJECTS.
CHECKED WITNESSES FROM L. 1, P. 77 & 164, S40°E TO POWER POLE 57.73'(R) S20°E TO NAIL IN POWER POLE 57.76' (M);
CHECKED WITNESSES FROM L. 2, P. 47, SOUTHEAST TO NAIL AND WASHER IN POWER POLE 57.76' (R&M); WEST TO NAIL AND CAP IN TEL. POLE 38.03' (R) 38.28' (M).
THE 3/8" REBAR WAS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6
REPLACED 3/8" REBAR WITH 5/8" X 24" LONG REBAR WITH ARENAC COUNTY REMONUMENTATION CAP.
EAST 2.0' TO PHYSICAL CENTERLINE OF DEEP RIVER ROAD
N 88°E 105.90' TO SET NAIL AND TAG IN TOP OF 8" PVC CULVERT
S 74°W 57.46' TO NORTHEAST CORNER OF POLE BUILDING
S 18°W 153.86' TO CENTERLINE OF HYDRANT
S 40°E 57.76' TO NAIL IN POWER POLE
WEST 38.28' TO NAIL AND CAP IN UTILITY POLE

Signed by Dale Winiecke
Surveyor's Michigan License No. 41915

Date 12/29/98



FB. 2, P. 67

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10 NOV 1998 Paul M. Cousey, Chairman