

APR 06 1999

ARENAC COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

ARENAC (County) Located In: Corner Code H-7 1. Public Land Survey T 18N R 4E 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R

Page 1 of 1 LC 2/ 178 ROSE SMITH ARENAC CO. REG. OF DEEDS RS Rec. Date 12/29/98 Time 10:51 RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, DALE L. WINIECKE, in a field survey on JULY 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column H and row 7.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-7 1. ORIGINAL POST SET IN 1943 BY J. BURT, D.S. HEMLOCK 6" S33°W 13 LINKS BIRCH 14" N75°W 20 LINKS 2. LCRC - L. 1, P. 185, BY N. CALDWELL, PS #12018, (1964) - FOUND ROTTED STAKE IN ROCKS, SET 1/2" IRON BAR 3. CERTIFICATE OF SURVEY, L.1, P.177, L. McGINNIS PS#18999, (1974) FOUND 1" PIPE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 SEARCHED APPARENT LOCATION AND FOUND 3/8" REBAR. EXCAVATED POINT AND FOUND 1 1/2" IRON 0.4' SOUTH OF THE 3/8" REBAR. CHECKED ONE REMAINING WITNESS, L.1, P.185, S22°E TO POWER POLE 55.76' (R), TO NORTHEAST FACE 55.98' (M) 1 1/2" IRON ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 REPLACED 1 1/2" REBAR WITH 5/8" X 24" LONG REBAR WITH ARENAC COUNTY REMONUMENTATION CAP. SOUTH 2.40' TO PHYSICAL CENTERLINE OF SAGATOO ROAD N50°E 29.52' TO SET NAIL & TAG IN EAST END OF 18" CMP N30°W 27.57' TO SET NAIL & TAG IN WEST END OF 18" CMP S80°W 177.30' TO SET NAIL & TAG IN NORTH FACE OF POWER POLE S60°E 120.98' TO SET NAIL & TAG IN SOUTHWEST FACE OF POWER POLE



Signed by Dale Winiecke Surveyor's Michigan License No. 41915

Date 12/28/98

FB. 2, P. 69

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 10 NOV 1998 Paul M. Ciosek LAUL M. GIOSEK P.S., CHAIRMAN