

**SURVEY & REMONUMENTATION**  
**APR 06 1995**  
**COMMISSION**

**Arenac County Remonumentation**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

02 PAGE 40  
 ARENAC COUNTY REGISTER OF DEEDS  
 29 12 35 PM '94  
 RECORDED

For corners in Arenac (County) Located In: Corner Code #

|                                    |                          |             |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey              | T <u>18N</u> R <u>4E</u> | <u>H 11</u> |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

I, Craig W. McVean, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H 11 Set 1/4 Section post - J. Burt - 1843.  
 W. Pine 30" S 19° E 20 L.  
 Hemlock 18" N 13° E 9 L.

Unrecorded Survey - Harrison Surveys #8105793 - found 3/8" bar with distance and angle ties East and South - 1981. MDOT ROW Sheet - Show H 11 as found with distance tie East to centerline Highway M 13.

Arenac County Survey Notes - Post and distance S. to H 13 - 1901.  
ACRC - Worth Road Plans and Notes - Distance and angle East & West - 1963.  
Recorded Survey - L. 1, P. 131 - Found - 1974.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H 11 Excavate 2' x 2' hole in centerline Worth Road - Find 3/8" x 18" rebar (Down 2') in line with fence to North and in agreement with ACRC road plans, recorded survey and unrecorded survey and distance tie E. to centerline Highway M-13. Monument accepted as the best available evidence of the position of the original corner.

Reference Pt. "A" - Found LS cap #27595 on iron on S. edge of bituminous of Worth Road. Iron appears to be on a line at a split distance between G 11 and I 11. Monument not in agreement with ACRC plans, recorded and unrecorded surveys or MDOT ROW sheet. Inquiry for information on monument was ignored. Monument was established using improper procedures and is not utilized as H 11-T18N-R4E in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H 11 Replace 3/8" rebar with 3" Arenac County brass cap on 5/8" x 24" rebar in mon. box.  
 S 35° W 31.79' (31.3' -R to centerline end CMP) to nail and tag in West end 36" CMP  
 N 63° E 28.12' to capped 3/8" rebar.  
 S 9° E 47.31' to capped 3/8" rebar.  
 N 3° E 38.80' to nail and tag in West side 10" Elm.  
 S 30°02' E 9.85' to Reference Pt. "A".

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT 'A' MEETING HELD ON 11-17-94  
Paul M. Ciosek  
 PAUL M. CIOSEK P.S., CHAIRMAN



Signed by Craig W. McVean Date 12/17/94  
 Surveyor's Michigan License No. 39088