

APR 06 1999

SECTION

ARENAC COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ARENAC (County) Located In: Corner Code # Page 1 of 1 ROSE SMITH ARENAC CO. REG. OF DEEDS RS Rec. Date 12/29/98 RECORDING FEES: 1. Public Land Survey T 18N R 4E I-6 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R

LC 2/ 177 1P ARENAC CO. REG. OF DEEDS Time 10:51 9.00

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, DALE L. WINIECKE, in a field survey on JULY 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. ORIGINAL POST SET IN JULY 1843 BY J. BURT, D.S. HEMLOCK 16" S 71° E 33 LKS. ELM 24" S 58 1/2° W 30 LKS. 2. LCRC L.1, P.179, N. CALDWELL, PS # 12018, (1964), FOUND 3/8" 3. CERTIFICATE OF SURVEY, L.1, P.69, L. MCGINNIS PS#18999, (1973), FOUND 3/4" PIPE 4. LCRC, L.1, P.39, L. MCGINNIS PS#18999, (1973), IRON 5. CERTIFICATE OF SURVEY, L.1, P.669, L. MCGINNIS PS#18999, (1989) FOUND 3/4" PIPE 6. CERTIFICATE OF SURVEY, L.1, P.660, L. MCGINNIS PS#18999, (1989) FOUND 3/8" IRON 7. CERTIFICATE OF SURVEY, L.2, P.100, T. LAPHAM PS#27595, (1995) FOUND 3/8" IRON 8. LCRC, L.2, P.98, S. KOCH PS#41103, (1997), FOUND 3/8" IRON

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column I and row 6.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 245 OF 1990 AT A MEETING HELD ON 10 Nov 1998 Paul M. Crosser

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT THE APPARENT LOCATION OF THE CORNER AND FOUND A 3/8" IRON. EXCAVATED UNDER POINT AND FOUND 3/8" BAR INSIDE OF THE 3/4" PIPE WITH ROCKS ON EITHER SIDE. NO OTHER OBJECTS WERE FOUND. CHECKED WITNESSES FROM L.2, P.98 AND FOUND THREE OF THE MEASUREMENTS TO BE THE SAME AS RECORD. WITNESS FROM L.2, P.100, CHECKED; S36°W TO U. POLE 128.27' (R) TO NAIL & TAG IN U. POLE 128.27'(M) ACCEPTED THE 3/8" REBAR AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 3/8" IRON WITH 5/8" X 24" LONG REBAR WITH ARENAC COUNTY REMONUMENTATION CAP

- SOUTH 2.2' TO PHYSICAL CENTERLINE OF IRWIN ROAD EAST 2.5' TO PHYSICAL CENTERLINE OF OLD M-10 S 45° E 201.34' TO NAIL AND TAG IN SOUTHWEST SIDE OF POWER POLE S 25° W 128.27' TO NAIL AND TAG IN NORTHWEST SIDE OF POWER POLE N 10° W 27.32' TO SET NAIL AND TAG IN EAST SIDE OF 20" ELM N 50° E 28.49' TO EAST END OF 18" CULVERT



Signed by Dale Winiecke

Date 12/28/98

Surveyor's Michigan License No. 41915

FB. 2, P. 71