

SURVEY & REMONUMENTATION

APR 06 1999

**ARENAC COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

ARENAC Located In: Corner Code Page 1 of 1
 (County) ROSE SMITH LC 2/ 171
18N R 4E 1-8 ARENAC CO. REG. OF DEEDS 1P
RS Rec. Date 12/29/98 Time 10:51
RECORDING FEES: 9.00

1. Public Land Survey T 18N R 4E _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number
 ARENAC CO. REG. OF DEEDS
 RS Rec. Date 12/29/98 Time 10:51
 RECORDING FEES: 9.00

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on NOVEMBER 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:


- I-8
- ORIGINAL POST SET IN JULY 1843 BY J. BURT, D.S.
HEMLOCK 26° S 73° E 21 LKS.
HEMLOCK 20° N 43° W 11 LKS.
 - LCRC, L.1, P.188, N. CALDWELL, PS #12018, (1964) SET 1/2" PIPE AND 1/2" BAR IN PAVEMENT FROM COUNTY SURVEY RECORDS
 - LCRC, L.2, P.100, S. KOCH, PS #41103, (1997) FOUND 1/2" BAR IN PAVEMENT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8
 SEARCHED AT THE APPARENT LOCATION OF THE CORNER AND FOUND A 1/2" PIPE IN PAVEMENT. EXCAVATED CORNER AND FOUND NO OTHER OBJECTS.
 CHECKED WITNESSES FROM L.1, P.188, N52°W TO R/W MARKER 60.60' (R) 60.45' (M); S65°W TO R/W MARKER 58.58' (R) 58.41' (M); N35°E TO SOUTHWEST CORNER OF RESTAURANT FOUNDATION 181.15 (R) 181.15' (M) NOTE: BUILDING IS NOW A HOUSE; EAST OF WEST EDGE OF CONCRETE PAVEMENT IN CENTERLINE OF ROAD WEST 15.2' (R&M).
 CHECKED WITNESSES FROM L.2, P.100 ALL MEASUREMENTS WERE IDENTICAL TO THE RECORD INFORMATION.
 ACCEPTED 1/2" PIPE AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8
 REPLACED 1/2" PIPE IN PAVEMENT WITH 5/8" REBAR WITH ARENAC COUNTY REMONUMENTATION CAP IN MONUMENT BOX
 N 60°W 57.00' TO NAIL AND TAG IN NORTHEAST SIDE OF POWER POLE
 EAST 64.17' TO NAIL AND TAG IN NORTH SIDE OF 20" POPLAR
 S 65°W 58.43' TO NAIL AND TAG IN TOP OF CONCRETE R/W MARKER
 N 35°E 181.15' TO SOUTHWEST CORNER OF FOUNDATION
 EAST 9.00' TO THE PHYSICAL CENTERLINE OF M-13
 SOUTH 2.20' TO THE PHYSICAL CENTERLINE BERNTHAL ROAD
 S54°E 11.09' TO PK NAIL & MDOT TAG USED FOR AERIAL TARGET
 EAST 15.20' TO THE WEST EDGE OF PAVEMENT IN THE CENTERLINE OF BERNTHAL ROAD TO THE WEST



Signed by Dale Winiecke

Date 12/28/98

Surveyor's Michigan License No. 41915

FB. 2, P. 87

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10 NOV 1998
Paul M. Glosek
 PAUL M. GLOSEK P.S., CHAIRMAN