

SURVEY & REMONUMENTATION

MAY 20 1997

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 002 PAGE 092

For corners in

Arenac (County)	Located in:	Corner Code #
1. Public Land Survey	T18N R 4E	I-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

ARENAC COUNTY
 REGISTER OF DEEDS
 RECORDED
 JAN 2 11 15 AM '97
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael J. MacDonald, in a field survey on October 10 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	5		5			4			3		2		1
3													
4	7		8			9			10		11		12
5													
6	10		17			16			15		14		13
7													
8	19		20			21			22		23		24
9													
10	30		29			28			27		26		25
11													
12	31		32			33			34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-10 Post set by J. Burt in 1843.
 L.C.R.C. - by Campbell, L. 1, P. 3 in 1977 - set PK nail.
 Recorded Surveys - by Edmands Engineering, L. 1, P. 561 - no call.
 Wade-Trim, L. 2, P. 121 - set PK nail.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Fnd PK nail.
 N 2621.82' to I-9 (2623.26' - R).
 S 2624.20' to I-11 (2623.26' - R).
 N 77° W 78.24' to nail and tag in pole (78.08' - R to pole) (78.8' - R to nail in pole).
 W 20.96' to centerline const joint (20.7' - R).
 SE 53.33' (53.31' - R) to nail in W leg of sign.
 SW 80.40' (80.31' - R) to nail in fence cor.
 NE 75.71' (75.68' - R) to nail in S face of 12" Pine.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Replaced PK nail with 5/8" x 24" rebar with Arenac County Remonumentation cap in monument box on E E.O.M. of M-13 pavement.

W 20.96' to construction centerline joint of M-13 pavement.
 S 59° E 53.33' to nail in W leg of sign.
 S 64° W 80.40' to nail in fence cor.
 N 77° W 78.24' to nail and tag in pole.
 N 68°30' E 75.71' to nail in S face of 12" Pine.
 Also fnd PK nail 6.5' N and 4.25' E of PK nail at I-10.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 25 Nov. 1996
 Paul M. Ciosek
 PAUL M. CIOSEK P.S., CHAIRMAN



Signed by Michael J. MacDonald
 Surveyor's Michigan License No. 22438

Date 19 Dec 96