

REMONUMENTATION  
 APR. 06 1995  
 COMMISSION

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 002 PAGE 033

For corners in

Arenac (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>4E</u>	<u>111</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED  
 Dec 29 12 35 PM '94  
 ARENAC COUNTY  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Craig W. McVean, in a field survey on September 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

111 Set post - J. Burt - 1843.  
 Hemlock 12" S 70° E 4 L.  
 Do. 13" N 36° W 39 L.

Arenac County Survey Notes - Distance tie E. - 1903.  
 Arenac County Survey Notes - Distance tie N. - 1903.  
 Arenac County Survey Notes - Section 26 - Distance tie N. - 1905.  
 Arenac County Road Plans - Worth Road - Distance Tie W. - 1963.

LCRC - L. 1, P. 3 - Monel rivet in pavement - Campbell - 1971.  
 Recorded Surveys - L. 1, P. 11 - Rivet - 1971; L. 1, P. 131 - thin bar - 1974; L. 1, P. 536 - iron - 1985; L. 1, P. 561 - nail and tag - 1987; L. 2, P. 1 - nail and tag in 1991; L. 2, P. 77 - found 1/2" rod - 1994.  
 Unrecorded Surveys - Harrison Surveys - #8105793 - set nail and tag - Sedgeman - 1981.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

111 Found pk nail per recorded surveys 1'± E. of physical centerline of Highway M-13. Excavated down to top box culvert. Found no evidence of Monel Rivet or 1/2" rod. Found recorded witness as follows:  
 N 75° W (R) 94.5' (95.35' -R, 94.45' -R) to face concrete project marker.  
 SW. 55.07' (55.6' -R) (55.06' -R) to NW. corner wingwall.  
 NE. 66.3' (65.52' -R) (66.2' -R) to nail in guy pole.  
 There appears to be slight discrepancy in witnesses for location of corner. Pk monument is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

111 Replace pk nail with 3" Arenac County brass cap on 5/8" x 24" rebar in mon. box.  
 S 68° W 67.65' to nail and tag in S. side U.P.  
 N 54° W 63.64' to nail and tag in corner fence post.  
 N 61° E 66.20' set nail and tag in U.P.  
 N 69° W 94.64' to centerline top concrete project marker.  
 S 74° E 119.72' to nail and tag in top W. guard rail post.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT "A" MEETING HELD ON 11-17-94  
 Paul M. Crossak  
 PAUL M. CROSEK P.S., CHAIRMAN



Signed by Craig W. McVean Date 12/21/94  
 Surveyor's Michigan License No. 39088