

APR 06 1999

ARENAC COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

ARENAC (County)

Located In:

Corner Code

Page 1 of 1 ROSE SMITH

LC 2/ 174 1P

1. Public Land Survey

T 18N R 4E

K-8

ARENAC CO. REG. OF DEEDS RS Rec. Date 12/29/98 Time 10:51 RECORDING FEES: 9.00

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, DALE L. WINIECKE, in a field survey on NOVEMBER 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is present at the intersection of row 8 and column J.

A. Description of original monument and accessories and/or subsequent restoration:

- K-8 1. ORIGINAL POST SET IN 1843 BY J. BURT, D.S. TAMARACK 8" S38°W 17 LINKS CEDAR 6" N43°E 3 LINKS

NO OTHER INFORMATION AVAILABLE


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-8 SEARCHED APPARENT LOCATION AND FOUND NO EVIDENCE OF THE CORNER SET CORNER MIDWAY AND ON LINE BETWEEN K-7 ARENAC CO. REMONUMENTATION L.2, P.131 AND K-9 ARENAC CO. REMONUMENTATION L.2, P.141.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-8 SET 5/8" X 24" LONG REBAR WITH ARENAC COUNTY REMONUMENTATION CAP.

N45°W 24.06' TO SET NAIL IN NORTHEAST FACE OF 8" MAPLE N10°E 70.21' TO SET NAIL IN EAST FACE OF 14" PINE S25°E 33.01' TO SET NAIL & TAG IN NORTH FACE OF 18" PINE S85°W 31.03' TO SET NAIL & TAG IN NORTH FACE OF 4" MAPLE EAST 12.5' TO CENTERLINE OF 4' SWALE DITCH NORTH 3' TO REMAINS OF WIRE FENCE



Signed by Dale Winiecke Surveyor's Michigan License No. 41915

Date 12/28/98

FB. 2, P. 78

ACCEPTED BY THIS ARENAC COUNTY SURVEY PRGR GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10 NOV 1998 Paul M. Ciosek, Chairman