

FEB 18 1994

Arenac County Remonumentation

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 02 PAGE 016
Dec 22 2 16 PM '93
RECORDED
ARENAC COUNTY REGISTER OF DEEDS

For corners in

<u>Arenac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>4E</u>	<u>J-11</u>
	T <u>18N</u> R <u>4E</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on September 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-11 Set post - J. Burt, 1843.
Maple 20" N 4-1/2° W 23 Lks.
Hemlock 8" S 39° W 6 Lks.

County surveyor notes - 1903 - Set cedar post with distance ties to K-11, I-11, and J-13, T18N, R4E. Recorded Surveys - L. 1, P. 366 - 1979; L. 1, P. 165 - 1974; L. 1, P. 378 - 1979; L. 1, P. 536 - 1985.

K-11 Set post - J. Burt, 1843.
Hemlock 14" N 8° W 4-1/2 Lks.
B. Ash 12" S 50-1/2° E 35 Lks.

County surveyor notes - 1903. Distance tie to J-11, T 18 N, R 4 E. L.C.R.C. - L. 1, P. 47 - McGinnis - 1973. Recorded Surveys - L. 1, P. 98 - 99 - 1973.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 Found 3/4" Iron pipe in mon. box per Recorded Survey - L. 1, P. 536. Monument in agreement with County surveyor distance to K-11, T18N, R4E. Monument accepted as the best available evidence of the position of the original corner. Accepted by Arenac County Peer Review Group on 11-17-93.

K-11 Found RR spike (spike in black top-R.) in mon. box per L.C.R.C. - L. 1, P. 47 and recorded surveys. Fits County surveyor notes distance to J-11, T18N, R4E. Monument accepted as the best available evidence of the position of the original corner. Accepted by Arenac County Peer Review Group on 11-17-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 Replaced 3/4" pipe with 3" Arenac County brass cap on 5/8" x 24" rebar in mon. box. N 33° E 36.93' to nail and tag in W face telephone brace post. S 63° E 69.68' to nail and tag in N side 10" Tamarack. S 12° E 91.40' to nail and tag in W side 8" Tamarack. S 35° W 40.49' (40.6' (R)) to centerline top 6' high chain link fence post in concrete.

K-11 Remove RR spike. Set 3" Arenac County brass cap on 5/8" x 24" rebar in mon. box. N 16° W 99.64' to nail and tag in E side U.P. N 76° E 63.60' to capped 3/8" rebar. S 77° W 68.34' to capped 3/8" rebar. S 15° W 193.20' to nail and tag in W'ly side U.P.



Signed by Craig W. McVean Date 12/20/93
Surveyor's Michigan License No. 39088