

**SURVEY &
REMONUMENTATION**

MAR 05 1998

**ARENAC COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

ARENAC
(County)

Located In: LINCOLN Corner Code L-9

1. Public Land Survey T18N R4E
T___ R___
T___ R___
T___ R___

2. Property Controlling in Section S___ T___ R___
S___ T___ R___

3. Miscellaneous Property in Sec. S___ T___ R___
S___ T___ R___

Page 1 of 1
ROSE SMITH
ARENAC CO. REG. OF DEEDS
RS Rec. Date 12/23/97 Time 11:37
RECORDING FEES: 9.00
LC 2/ 127
IP

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, MICHAEL J. MACDONALD, in a field survey on OCTOBER 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-9
- ORIGINAL POST SET J. BURT D.S. JULY 1843
WHITE PINE 14° S 31°W 16 LINKS
TAMARACK 6° N 40 1/2°W 15 LINKS
 - SURVEY, L. 1, P. 197, MCGINNIS, 1975, 3/8" REROD
SURVEY, L. 1, P. 181, MCGINNIS, 1975, FND 3/8" REROD
NE 42.6' 8" MAPLE
N 60° E 81.65' TO 8" BIRCH
SW 37.1' TO STOP SIGN
 - MDOT WITNESS CARD, KOCH, 1995, FND 3/8" REROD
N 45° E 42.40' N/T S. SIDE 12" MAPLE
N 60° E 82.04' N/T NW SIDE 24" BIRCH
S 45° E 48.97' N/T SW SIDE FENCE POST
N 50° W 82.56' N/T NE SIDE PP
S 45° W 39.83' FACE OF SIGN POST
 - SURVEY. KOBS L. 2, P. 128, FND 3/8" REROD, NO WIT.
 - SURVEY, L., P. 1, MCGINNIS, 1995, NO CALL

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND A 3/8" REROD AND A 1/2" REROD (12.5' SOUTH AND 4' EAST) USED IN SURVEY L. 2, P. 155 PER WITNESSES. WITNESSES FROM MDOT WITNESS CARD AND SURVEYS, L. 1, P. 197, L. 1, P. 181 FIT THE LOCATION OF THE 3/8" IRON. 3/8" IRON ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9
REPLACED THE 3/8" REROD WITH 5/8" REROD x 24" LONG REROD WITH ARENAC CO. REMONUMENTATION CAP.
N 45° E 42.48' (42.40' R.) N/T S. SIDE 12" MAPLE
N 70° E 82.23' (82.04' R.) N/T NW SIDE 24" BIRCH
S 45° E 48.99' (48.97' R.) N/T SW SIDE FENCE POST
N 50° W 82.63' (82.56' R.) N/T NE SIDE PP
N 60° 28.32' NE FACE STOP SIGN

Signed by Michael J. MacDonald
Surveyor's Michigan License No. 22438
FIELDBOOK # 2, PAGE 54



Date 22 Dec 97

ACCEPTED BY THIS ARENAC COUNTY SURVEY PIER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT "A" MEETING HELD ON 10/31/97
Paul M. Ciosek
PAUL M. CIOSEK, SURVEYOR

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 197
REVISED JAN., 198
REVISED OCT., 198