

APR 06 1999

SECTION

ARENAC COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ARENAC (County)

Located In:

Page 1 of 1 Corner Code # ROSE SMITH

LC 2/ 167 1P

ARENAC CO. REG. OF DEEDS RS Rec. Date 12/29/98 Time 10:51 RECORDING FEES: 9.00

- 1. Public Land Survey T 18N R 4E T 18N R 5E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, DALE L. WINIECKE, in a field survey on NOVEMBER 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Cell (8, M) contains a dot.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- M-8 1. ORIGINAL POST SET IN 1837 BY L. CLASON, D.S. HEMLOCK 8" N84°W 10 LINKS 2. CERTIFICATE OF SURVEY, L.1, P.4, G. DeLaMATER PS#13030, (1971), SET IRON MIDWAY AND ON LINE BETWEEN M-7 AND M-9.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 SEARCHED APPARENT LOCATION AND FOUND 3/8" REBAR. WITNESS PER L.1, P.4 NORTHEAST 63.2' TO 12" MAPLE (R); N36°E 63.92' TO SET & TAG IN SOUTHEAST FACE OF 18" MAPLE (M) 3/8" REBAR ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 REPLACED 3/8" REBAR WITH 5/8" X 24" LONG REBAR WITH ARENAC COUNTY REMONUMENTATION CAP S36°W 88.83' TO SET NAIL & TAG IN NORTH FACE OF 12" MAPLE S04°E 121.85' TO SET NAIL & TAG IN NORTHEAST FACE OF 20" POPLAR N36°E 63.92' TO SET NAIL & TAG IN SOUTHEAST FACE OF 18" MAPLE N60°W 77.18' TO SET NAIL & TAG IN SOUTH FACE OF POWER POLE N30°W 42.07' TO NAIL IN SOUTHWEST FACE OF TELEPHONE POLE N52°E 43.00' TO NAIL IN THE CROTCH OF A 24" BOX ELDER NORTH 13' TO CENTERLINE OF DITCH RUNNING WEST EAST 2' TO PHYSICAL CENTERLINE OF FOCO ROAD



Signed by Dale Winiecke Date 12/28/98 Surveyor's Michigan License No. 41915

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10 NOV 1998 Paul M. Gusek P.S., CHAIRMAN