

SURVEY & REMONUMENTATION

APR 06 1995

COMMISSION

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **02** PAGE **42**

For corners

Arenac

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 18N R 4E M 11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

ARENAC COUNTY REGISTER OF DEEDS
 Dec 29 12 35 PM '94
 RECORDED

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Craig W. McVean, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M 11 Set post corner to Section 25 & 36 - L. Clason - 1837.
Swamp Oak 18" S 19° W 18 L.
Birch N 67-1/2° W 12 L.

LCRC - L.1, P. 47 - 5/8" iron - McGinnis - 1973.
Recorded Survey - L. 1, P. 98 - Found 5/8" iron - 1973; L. 1, P. 152 - 1974; L. 1, P. 367 - 1978; L. 1, P. 579 - 1987
Unrecorded Survey - Edmands Engineering (Now Wade-Trim) #5377 - 1968

Arenac County Survey Notes - Section 31 - T18N - R5E - North, East, & South - 1905.
ACSN - Section 30 - T18N, R5E - witness and distance to B 11 to East - 1905.
ACSN - Section 30 - T18N, R5E - Large stone about 20" and small cedar post under stone - distance tie to B 11 and L 11.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M 11 Standard Section corner common to Section 25 and 36, T18N, R4E and Section 30 and 31, T18N, R5E. Found 3/4" (5/8" -R) iron rod per LCRC and surveys. Excavate find 3 - 5" diameter granite stones along W. side of iron rod - remove stone and iron rod - found 1-1/4" O.D. x 1.6' long iron pipe under 3/4" rod - down 1.9' - remove pipe and found 20"± large granite stone on N. side of removed pipe per County Surveyor notes - Down 2.2'. Monument accepted as a careful and faithful perpetuation of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M 11 Removed iron rod, 3 stones and iron pipe. Leave large stone in place and set 3" Arenac County Brass Cap on 5/8" x 24" rebar in mon. box at location of iron rod and pipe on S. side of stone for corner.
S 72° W 120.19' (120.2' -R) to set nail and tag in N. side U.P.
S 53° W 49.33' (49.2' R & M to face) to chiseled "X" on top concrete project marker.
S 6° E 44.15' to capped 3/8" rebar.
N 77° E 27.11' to capped 3/8" rebar.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT 'A' MEETING HELD ON 11-17-94
Paul M. Ciosek
PAUL M. CIOSEK PS., CHAIRMAN

Signed by Craig W. McVean
Surveyor's Michigan License No. 39088

Date 12/17/94