

**ARENAC COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 25 2000

For corners in

<u>ARENAC COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>5E</u>	<u>B-5</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

SECTION

Page 1 of 1  
ROSE SMITH  
ARENAC CO. REG. OF DEEDS  
RS Date 01/06/2000  
RECORDING FEES:  
LC 2/202  
1P  
Time 10:06:54  
9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, DALE L. WINIECKE, in a field survey on NOVEMBER, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-5  
POST SET BY J. BURT, JULY 1843  
7" SPRUCE N 82°E 7 LINKS  
6" SPRUCE S57°W 16 LINKS

FIELD NOTES FROM WADE-TRIM/EDMANDS CERTIFICATE OF SURVEY RECORDED IN L. 2, P. 70, PAUL M. CIOSEK, PS#25835, FOUND 1/2" IRON.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5  
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND A 3/8" REROD.  
FOUND NO RECORDED INFORMATION FOR THIS CORNER.  
VERIFIED WITNESSES FROM WADE-TRIM/EDMANDS FIELD NOTES, SW 83.2'(R) TO PK NAIL IN WEST FACE OF TWIN 18" OAK, SET NAIL & TAG IN WEST FACE TWIN 18" OAK 83.38' (M), S5°E 32.9'(R) TO PK NAIL IN UTILITY POLE #2735, SET NAIL AND TAG IN WEST FACE U. POLE 33.15' (M). EXCAVATED POINT AND FOUND NO OTHER MONUMENTATION.  
THE 3/8" REROD WAS ACCEPTED AS THE BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5  
REPLACED THE 3/8" REROD WITH 5/8"x 24" LONG REROD WITH ARENAC COUNTY REMONUMENTATION CAP.  
S04°E 33.15' TO SET NAIL AND TAG IN WEST FACE OF UTILITY POLE #2735  
S14°E 52.69' TO SET NAIL AND TAG IN W'LY FACE 18" OAK  
N08°W 18.50' TO SET NAIL AND TAG IN SW'LY FACE OF FENCE POST  
N26°E 31.74' TO SET NAIL AND TAG IN SE'LY FACE 8" WALNUT  
N72°W 38.78' TO SET IRON AND CAP PS#41915  
SOUTH +/- 5' TO CENTERLINE OF PALMER ROAD

Signed by Dale Winiecke  
Surveyor's Michigan License No. 41915

Date 12/30/99



ACCEPTED BY THE ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON NOV 9, 1999  
Paul M. Ciosek  
PAUL M. CIOSEK, PS, CHAIRMAN