

SURVEY & REMONUMENTATION
 APR 06 1995
 COMMISSION

Arenac County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **02** PAGE **41**

For corners in

<u>Arenac</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>5E</u>	<u>B 11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

ARENAC COUNTY REGISTER OF DEEDS
 Dec 29 12 36 PM '94
 RECORDED

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	●												
12	31	32	33	34	35	36							
13													

I, Craig W. McVean, in a field survey on July 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B 11 Set 1/4 Section post - J. Burt - 1843.
 B. Ash 20" S 7° E 24 L.
 Cedar 12" N 81-1/2° W 44 L.

Recorded Survey - L. 1, P. 152 - found iron - 1974; L. 1, P. 358 - found pk nail - 1978; L. 1, P. 438-444 - 1981; L. 1, P. 615 - 1987.
Unrecorded Survey - Edmands Engineering (Wade-Trim) #5377 - 1968.

Arenac County Survey Notes - Section 31, T18N, R5E - 1905.
 ACSN - Section 30, T18N, R5E - witness and distance to A 11 - 1905.
 ACSN - North Drain - Cedar post with 1 peck of small stones around with witness and distance to A 11 - 1922.
 LCRC - L. 1, P. 101 - pk nail - McGinnis - 1977.
 LCRC - L. 1, P. 123 - pk nail - Sedgeman - 1978.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B 11 Found pk nail at centerline of Worth Road per LCRC's, recorded surveys and unrecorded surveys. Distance to A 11 in agreement with 1905 ACSN and within 3' of 1922 ACSN's - Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B 11 Replace pk nail with 3" Arenac County brass cap on 5/8" x 24" rebar in mon. box.
 S 25° W (S 10° W -R) 106.65' (105.5 (m) - 105.8 -R) to face) to set nail and tag in E. side 24" (18"-R) Maple.
 S 79° W (S 70° W -R) 105.33' (105.9 (M) 105.94' -R) to centerline) to set nail and tag in N. side 20" (16" -R) Basswood.
 N 73° E 172.88' to top of W. bolt with chiseled "x" on base of S. tower leg.
 N 62° W 36.04' to capped 3/8" rebar.
 S 65° W 206.25' to NE corner block foundation House #2765.

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-17-94
Paul M. Ciosek
 PAUL M. CIOSEK P.S., CHAIRMAN



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 12/17/94