

**ARENAC COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 25 2000

For corners in

ARENAC COUNTY
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 18N R 5E _____ C-5
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

SECTION

Page 1 of 1
 ROSE SMITH
 ARENAC CO. REG. OF DEEDS
 RS Date 01/06/2000
 RECORDING FEES: _____

LC 2/204
 1P
 Time 10:08:21
 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on NOVEMBER, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5			●										
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-5
 POST SET BY J. BURT, JULY 1843
 20" ELM N75°W 7 LINKS
 13" ELM S51°E 24 LINKS

FIELD NOTES FROM WADE-TRIM/EDMANDS CERTIFICATE OF SURVEY RECORDED IN L. 2, P. 70, PAUL M. CIOSEK, PS #25835, JUNE 1993, FOUND 3/4" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5
 SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND 3/8" IRON.
 CHECKED WITNESSES FROM WADE-TRIM FIELD NOTES, SOUTHWEST TO MDOT TAG IN POWER POLE 59.23' (R) 59.27' (M); N30°W TO MDOT TAG IN METER POLE 49.47' (R) 49.55' (M); N35°E TO MDOT TAG IN UTILITY POLE 43.71' (R) 43.75' (M), N52°E TO MDOT TAG IN APPLE TREE 73.68' (R) 73.67' (M).
 EXCAVATED POINT AND FOUND 3/8" INSIDE 3/4" PIPE. EXCAVATED FURTHER AND FOUND NO OTHER MONUMENTATION.
 3/8" IRON INSIDE 3/4" PIPE ACCEPTED AS THE BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5
 REPLACED THE 3/8" IRON WITH 5/8"x 24" LONG REROD WITH ARENAC COUNTY REMONUMENTATION CAP.
 N22°W 49.55' TO MDOT TAG IN METER POLE
 S56°W 59.27' TO MDOT TAG IN UTILITY POLE
 N44°E 43.75' TO MDOT TAG IN UTILITY POLE
 N62°E 73.67' TO MDOT TAG IN APPLE TREE
 S66°E 45.78' SET 1/2" REROD WITH PS CAP 41915
 S14°E 43.90' SET 1/2" REROD WITH PS CAP 41915
 SOUTH 1' +/- TO PHYSICAL CENTERLINE OF PALMER ROAD
 WEST 1' +/- TO PHYSICAL CENTERLINE OF LENTZ ROAD



Signed by Dale Winiecke
 Surveyor's Michigan License No. 41915

Date 12/30/99

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON NOV 19, 1999
Paul M. Ciosek
 PAUL M. CIOSEK, CHAIRMAN