

**ARENAC COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 25 2000

For corners in

ARENAC COUNTY
(County)

Located In: Corner Code #

SECTION

1. Public Land Survey T 18N R 5E C-7
 T ___ R ___
 T ___ R ___
 T ___ R ___
 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

Page 1 of 1

ROSE SMITH

ARENAC CO. REG. OF DEEDS

RS Date 01/06/2000

RECORDING FEES:

LC 2/206

1P

Time 10:09:22

9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on JULY, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-7
 POST SET BY J. BURT, JULY 1843
 10" ELM S45°E 31 LINKS
 20" BLACK ASH N45°W 34 LINKS

CERTIFICATE OF SURVEY, L. 1, P. 288, HERBERT L. FLUHARTY, PS #18223, SEPTEMBER 1976, FOUND 1" BAR
 LCRC, L. 1, P. 94, HERBERT L. FLUHARTY, PS #18223, SEPTEMBER 1976, FOUND 1" BAR
 FIELD NOTES FROM WADE-TRIM/EDMANDS CERTIFICATE OF SURVEY RECORDED IN L. 2, P. 70, PAUL M. CIOSEK, PS#25835, JUNE 1993, FOUND 3/4" IRON.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7
 SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND 1" BAR.
 CHECKED WITNESSES, WITNESSES FROM WADE TRIM FIELD NOTES: S65°E TO NORTHEAST CORNER OF HOUSE 107.42' (R) 106.7' (M); S47°E TO SOUTHWEST CORNER OF HOUSE 113.35' (R) 113.3' (M). S60°W TO FACE OF POWER POLE 162.35' (R) 162.3' (M).
 EXCAVATED UNDER 1" BAR AND FOUND CEDAR POST.
 THE 1" BAR IN THE CEDAR POST WAS ACCEPTED AS THE BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7
 REPLACED THE 1" BAR WITH 5/8"x 24" LONG REROD WITH ARENAC COUNTY REMONUMENTATION CAP.
 N52°W 31.20' TO NAIL AND TAG IN SOUTH FACE OF SOUTHERLY TRIPLE ELM.
 S68°W 162.55' TO NAIL AND TAG IN EAST FACE POWER POLE
 S10°W 87.79' TO NAIL AND TAG IN WEST FACE MAILBOX POST
 S12°E 111.69' TO NAIL AND TAG IN EAST FACE OF FENCE POST
 N60°E 38.68' TO NOTCH IN WEST END 48" CMP
 EAST 6' ± TO PHYSICAL CENTERLINE OF LENTZ
 SOUTH 3' ± TO PHYSICAL CENTERLINE OF SAGATOO ROAD

ACCEPTED BY THE ARENAC COUNTY SURVEY DEPARTMENT AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Nov 9, 1999
Paul M. Ciosek
 PAUL M. CIOSEK, CHAIRMAN



Signed by Dale Winiecke

Date 12/30/99

Surveyor's Michigan License No. 41915