

**ARENAC COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED  
JAN 25 2000

For corners in

<u>ARENAC COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>5E</u>	<u>C-8</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

SECTION

Page 1 of 1  
ROSE SMITH  
ARENAC CO. REG. OF DEEDS  
RS Date 01/06/2000  
RECORDING FEES:

LC 2/207  
1P  
Time 10:09:45  
9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, DALE L. WINIECKE, in a field survey on JULY, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-8  
POST SET BY J. BURT, JULY 1843  
10" BLACK ASH N17°E 21 LINKS  
20" BLACK ASH S11°W 8 LINKS

LCRC, L. 1, P. 94, HERBERT L. FLUHARTY, PS #18223, SEPTEMBER 1976, FOUND 3/4" BAR  
CERTIFICATE OF SURVEY, L. 1, P. 288, HERBERT L. FLUHARTY, PS #18223, SEPTEMBER 1976, FOUND 3/4" BAR  
UNRECORDED SURVEY, EDMANDS ENGINEERING, 1963, 1/2" PIPE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8  
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND 3/4" BAR.  
CHECKED WITNESSES FROM LCRC L. 1, P. 94, S88°E TO TP 29.08(R) TO FACE OF U. POLE 28.79' (M); S65°W TO C/L WEST END 10" TUBE 17.77' (R) 17.99' (M); N80°E TO N. END CIRCULAR SLAB UNDER PUMP SHED 50.62' (R) 50.90' (M). CHECKED EDMANDS ENGINEERING WITNESSES S08°E TO FACE T. POLE 186.7' (R&M).  
EXCAVATED POINT AND FOUND NO OTHER MONUMENTATION.  
THE 3/4" BAR WAS ACCEPTED AS THE BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8  
REPLACED THE 3/4" BAR WITH 5/8"x 24" LONG REROD WITH ARENAC COUNTY REMONUMENTATION CAP.  
S12°W 107.59' SET NAIL AND TAG IN WEST FACE MAILBOX POST  
S12°E 186.99' SET NAIL AND TAG IN EAST FACE TELEPHONE POLE  
S22°W 110.64' TO CHISELED "X" ON NORTH END OF 55" CONCRETE PIPE  
S26°W 194.52' TO NE CORNER OF FOUNDATION HOUSE #4778  
S78°W 17.91' TO CHISELED "X" IN 12" CONCRETE PIPE  
S84°E 29.14' SET NAIL AND TAG IN SOUTH FACE TELEPHONE POLE  
EAST 3' +/- TO PHYSICAL CENTERLINE LENTZ ROAD

Signed by Dale Winiecke  
Surveyor's Michigan License No. 41915

Date 12/30/99

