

**ARENAC COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

JAN 25 2000

For corners in

<u>ARENAC COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>5E</u>	<u>D-7</u>
	T ___ R ___	Page 1 of 1
	T ___ R ___	ROSE SMITH
	T ___ R ___	ARENAC CO. REG. OF DEEDS
2. Property Controlling in Section	S ___ T ___ R ___	RS Date 01/06/2000
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	RECORDING FEES: 9.00

SECTION

LC 2/209
1P

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DALE L. WINECKE, in a field survey on JULY, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4	3				2			1
3												
4	7	8		9	10				11			12
5												
6	18	17		16	15				14			13
7												
8	19	20		21	22				23			24
9												
10	30	29		28	27				26			25
11												
12	31	32		33	34				35			36
13												

NOTE: Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-7
POST SET BY J. BURT, JULY 1843
14" CEDAR S1 1/2°E 28 LINKS
15" CEDAR N9 1/2°E 8 LINKS

EDMANDS ENGINEERING NOTES 1965, 1 1/2" PIPE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND 1 1/2" PIPE.
FOUND NO RECORDED INFORMATION FOR THIS CORNER.
CHECKED WITNESSES FROM EDMANDS ENGINEERING NOTES SW TO ROAD SIGN 36.25' (R) 38.95' (M); NORTH TO C/L CULVERT 18.75' (R) TO SET PK NAIL IN C/L 48" CMP 18.99' (M); E.N.E. TO T. POLE 35.3' (R) TO FACE U.POLE 35.32' (M)
EXCAVATED POINT AND FOUND NO OTHER MONUMENTATION
1 1/2" PIPE WAS ACCEPTED AS THE BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7
REPLACED THE 1 1/2" PIPE WITH 5/8"x 24" LONG REROD WITH ARENAC COUNTY REMONUMENTATION CAP.
N02°E 18.95' TO PK NAIL IN WEST END 48" CMP
N08°E 27.67' TO PK NAIL IN NE FACE OF 15" ASH
S68°E 76.48' TO PK NAIL IN WEST END 12" CMP
N36°E 35.41' TO NAIL AND TAG IN NW FACE 8" POST
S38°E 46.61' TO TOP CENTER OF TELEPHONE RISER
S42°W 39.18' TO PK NAIL IN SOUTH END 15" CMP
EAST ±6' TO PHYSICAL CENTERLINE OF LAFAVE ROAD
SOUTH ±3' TO PHYSICAL CENTERLINE OF SAGATOO ROAD



Signed by Dale Winecke
Surveyor's Michigan License No. 41915

Date 12/30/99

