

**ARENAC COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

JAN 25 2000

SECTION

ARENAC COUNTY Located In: Corner Code #
(County)

1. Public Land Survey T 18N R 5E E-7
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Page 1 of 1
ROSE SMITH
ARENAC CO. REG. OF DEEDS
RS Date 01/06/2000 Time 10:12:31
RECORDING FEES: 9.00

LC 2/213
1P

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DALE L. WINIECKE, in a field survey on JULY, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-7
POST SET BY J. BURT, JULY 1843
12" CEDAR S62°W 33 LINKS
24" ELM S30°E 18 LINKS

LCRC, L. 1, P. 134, LEONARD URBANIAK, PS#14469, JUNE 1979, FOUND 5/8" BAR
PLAT OF GREAT LAKES SHORES MARINA, L. 3, P.7
CERTIFICATE OF SURVEY, L. 2, P. 25, LLOYD MCGINNIS, PS#18999, AUGUST 1992, FOUND BENT 3/8" REROD, RESET REROD AND CAP
CERTIFICATE OF SURVEY, L. 1, P.554, PAUL M. CIOSEK, PS#25835, JUNE 1986, FOUND 1/2" PIPE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND 3/4" PIPE.
CHECKED WITNESSES FROM LCRC L. 1, P. 134, S50°E TO POWER POLE 62.75' (R) TO NAIL & TAG IN NORTHEAST FACE 62.78' (M); S30°W TO POWER POLE 64.5' (R) TO NAIL & TAG IN EAST FACE 64.50' (M); N48°W TO POWER POLE 47.50' (R) TO NAIL & TAG IN U. POLE 47.55' (M).
CHECKED WITNESSES FROM CERT. OF SURVEY, L. 2, P. 25, WNW TO CAPPED NAIL IN SOUTH SIDE TWIN 15" ASH 74.94' (R) 74.90'(M); SE TO NAIL & TAG #9433 IN U. POLE 62.76' (R) 62.78' (M); SW NAIL; & TAG #9433 IN U. POLE 64.45' (R) 64.50' (M).
CHECKED WITNESSES FROM CERT. OF SURVEY, L. 1, P.554, NW TO P.POLE 46.70' (R) TO NAIL; & TAG IN U. POLE 47.55' (M).
EXCAVATED POINT AND FOUND NO OTHER MONUMENTATION.
ALSO FOND NAIL 8' SOUTH OF 3/4" PIPE. EXCAVATED POINT AND FOUND NO OTHER MONUMENTATION
3/4" PIPE ACCEPTED AS THE BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7
REPLACED THE 3/4" PIPE WITH 5/8"x 24" LONG REROD WITH ARENAC COUNTY REMONUMENTATION CAP.
N50°W 47.55' TO NAIL AND TAG IN POWER POLE
S40°W 64.50' TO NAIL AND TAG IN EAST FACE OF POWER POLE
S50°E 62.78' TO NAIL AND TAG IN NORTHEAST FACE OF POWER POLE
S45°E 133.45' TO SE CORNER OF PORCH
N60°W 74.90' TO CAP AND NAIL IN TWIN ASH
S 30°E 93.45' SET MAG NAIL IN NORTH FACE OF SOUTHERLY POLE IN LANDSCAPE AREA
SOUTH 8.00' TO FOUND NAIL
SOUTH 7' +/- TO PHYSICAL CENTERLINE OF SAGATOO ROAD
EAST 1' +/- TO PHYSICAL CENTERLINE OF LACLAIR ROAD

ACCEPTED BY THIS ARENAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON Nov 9, 1999
Paul M. Ciosek
PAUL M. CIOSEK, PS, CHAIRMAN



Signed by Dale Winiecke Date 12/30/99

Surveyor's Michigan License No. 41915