

**ARENAC COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 25 2000

For corners in

ARENAC COUNTY Located In: Corner Code #  
(County)

1. Public Land Survey T 18N R 5E F-5  
T      R            
T      R            
T      R          

2. Property Controlling S      T      R            
in Section S      T      R          

3. Miscellaneous S      T      R            
Property in Sec. S      T      R          

SECTION

Page 1 of 1  
ROSE SMITH  
ARENAC CO. REG. OF DEEDS  
RS Date 01/06/2000 Time 10:13:20  
RECORDING FEES: 9.00

LC 2/215  
1P

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, DALE L. WINIECKE, in a field survey on DECEMBER, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5						●							
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-5  
POST SET BY J. BURT, JULY 1843  
8" CEDAR N 75°E 7 LINKS  
6" TAMARACK N 45°W 11 LINKS

CO. SUR NOTES 1904 FB 4, PAGE 2 FOR SECTION 9  
CO. SUR NOTES 1907 PAGE 25 NOTES FOR THE WEST 1/2 OF SECTION 9.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5  
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND NO MONUMENTATION.  
CORNER WAS SET MIDWAY AND ON LINE BETWEEN THE CORNERS E-5 AND G-5  
POSITION FALLS ON TREE LINE AND DITCH TO THE NORTH.  
THE REESTABLISHED POINT WAS ACCEPTED AS THE BEST EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5  
SET 5/8"x 24" LONG REROD WITH ARENAC COUNTY REMONUMENTATION CAP.  
S55°W 45.78' TO NAIL AND TAG IN 5" TREE  
S25°W 24.83' TO NAIL AND TAG IN 5: TREE  
NORTH 21.43' TO SET 1/2" IRON WITH CAP PS#41915  
N45°E 44.73' TO SET 1/2" IRON WITH CAP PS#41915  
NORTH +/- 5' TO CENTERLINE OF PALMER ROAD

Signed by Dale Winiecke  
Surveyor's Michigan License No. 41915

Date 12/30/99

