

**ARENAC COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

JAN 25 2000

For corners in

<u>ARENAC COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>5E</u>	<u>G-5</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous	S ___ T ___ R ___	___
Property in Sec.	S ___ T ___ R ___	___

SECTION

Page 1 of 1
ROSE SMITH

LC 2/216
1P

ARENAC CO. REG. OF DEEDS
RS Date 01/06/2000
RECORDING FEES:

Time 10:13:51
9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, DALE L. WINIECKE, in a field survey on NOVEMBER, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same Town and Range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-5
POST SET BY J. BURT, JULY 1843
14" ASH S24°E 149 LINKS
9" TAMARACK S81°E 2.03 CHAINS

PLAT OF TIMBER ISLAND CALLS FOR POINT AS POINT OF COMMENCEMENT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5
SEARCHED THE APPARENT LOCATION OF THE CORNER AND FOUND 3 POINTS.
EXCAVATED POINT #1 1 1/2" PIPE WITH 1 1/2" PIPE 0.3' SOUTH OF POINT #1. FOUND CEDAR POST 0.3' WEST & 0.3' SOUTH OF POINT #1.
EXCAVATED POINT #2 1 1/2" PIPE AND FOUND NO OTHER MONUMENTATION,
CEDAR POST BETWEEN TWO 1 1/2" PIPES ACCEPTED AS BEST EVIDENCE OF ORIGINAL CORNER.
SET 5/8"x 24" LONG REROD WITH ARENAC COUNTY REMONUMENTATION CAP OVER LOCATION OF CEDAR POST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5
SET 5/8"x 24" LONG REROD WITH ARENAC COUNTY REMONUMENTATION CAP.
S48°E 33.19' TO NAIL & TAG IN NORTHEAST FACE 12" ASH
S62°E 62.12' TO NAIL & TAG IN NORTHEAST FACE 14" ASH
N78°E 51.44' TO SET IRON W/ CAP PS #41915
N78°E 5.78' TO FOUND 1 1/2" PIPE
N58°W 39.00' TO SET IRON W/ CAP PS #41915
S72°W 37.88' TO SET IRON W/ CAP PS #41915

Signed by Dale Winiecke
Surveyor's Michigan License No. 41915

Date 12/30/99

