

LAND CORNER RECORDATION CERTIFICATE

+ Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Arenac</u> (County)	Located In T <u>19N</u> R <u>3E</u>	Corner Code # <u>G1</u>
1. Public Land Survey T _____ R _____	T _____ R _____	_____
2. Property Controlling in Section S _____ T _____ R _____ S _____ T _____ R _____	T _____ R _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Section S _____ T _____ R _____ S _____ T _____ R _____	T _____ R _____ T _____ R _____	_____ _____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Aug. 18, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G1 – GLO – Intersect Townline 46 L. East of Cor. Sects. 33 & 34 Town N. of this.
 Set post at intersection – J. Mullett – 1846
 Tamarack 6" S8°W 48 L.
 Tamarack 6" S10°E 60 L.
 - MDOT Wit. Card – C. F. Roser – 1965
 (LCRC – L. 1, p. 229 – 1984)
 Set 2" pipe – 5' long w/ 18" above ground.
 Marked Cedar post. Corner set by single proportion.
 6" Poplar N67°W 81.79'; 5" Poplar N27°W 44.88';
 7" Poplar N43°E 36.36'; 7" Poplar N72°E 27.12'
 S89° 52' 50" W 30.43' to 'G13', T20N, R3E

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G1 – Closing corner common to Sec. 3 & 4, T19N, R3E – Fd. 2" iron pipe – Top 2' Rust off at ground level – per MDOT in swamp on the standard line. No GLO evidence. 2" pipe accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G1 – Drove stamped 2" Alum. Cap on 5/8" x 4' long iron rebar into centerline of Fd. 2" pipe
 Set Blue Carsonite Post 1' S
 S67°E 33.43' to set 18" long 'T' iron
 S19°W 50.18' to set 1/2" x 2.7' long iron rebar
 N18°W 47.25' to set 1/2" x 30" long iron rebar
 West 30.49' to 'G13' – T20N, R3E – 2" Alum. Cap in 2" pipe



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 2/7/2005