

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

| | | |
|--|--------------------------|---------------|
| For Corners In: <u>Arenac</u> (County) | Located In | Corner Code # |
| 1. Public Land Survey | T <u>19N</u> R <u>3E</u> | <u>I-1</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Dec. 8, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- I-1 - GLO - Intersected Town line 40 L. '113', T20N, R3E
 - East of corner Sec. 34 & 35. Set post at intersection - J. Mullett - 1846
 - W. Pine 6" S58°W 13 L.
 - Aspen 4" S38°E 11 L.
 - MDOT Wit. Card - C. F. Roser - 1965 (LCRC L. 1, p. 226 - 1984) - Set ¾" pipe. Direction controlled by fd. Sec. Cor. and sub'n a mile to the east and distance was set
 - Rec. by GLO. Marked cedar guard post.
 - 20" Red Pine S3°W 68.60'; 24" W. Pine S44°W 83.29'; 20" Oak S75°W 68.85'; S89° 45'53" W 26.40' to
- Rec. Sur - L. 2, p. 371 - J. C. Kapelczak - 2000 - Fd. ¾" iron pipe; MDOT wit. tag W. side 30" R. Pine S3°W 68.58'; spike SE side 36" W. Pine S44°W 82.84'; Spike N side 28" Oak S75°W 68.78'; spike W. side 14" J. Pine North 24.97'; spike S. side 18" W. Pine West 7.01'
- Rec. Sur. - L. 2, p. 369 - B. Woods - 2000 Fd. ¾" pipe; S3°W 68.60' - 28" R. Pine (Fd. nail) S44°W 83.29'; 36" W. Pine (Fd. nail) S75°W 68.85' - 28" Oak (Fd. nail); S66° 6.98' - 18" Sco. Pine West 26.80' ½" iron rod (I13, T20N, R3E)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-1 - Closing corner common to Sec. 2 & 3, T19N, R3E - Fd. ¾" I. D. iron pipe per MDOT and Record Surveys. No GLO evidence. Centerline of N-S Gravel Rd. is 27'± W. 2-track ENE'ly is 9'± N. ¾" iron pipe accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-1 - Drove stamped 2" Alum. Cap on 5/8" x 1.9' long iron rebar into center of Fd. ¾" iron pipe.
 - S66°E 7.02' to Fd. Nail in S. side 20" J. Pine scribed 'CCBT' (JCK, BW)
 - S75°W 68.80' to Fd. Nail in N. side 26" Oak (MDOT, JCK, BW)
 - N4°W 25.01' to Fd. Nail in W. side 14" J. Pine (JCK)
 - S40°W 83.29' to set N & T in NW side 30" W. Pine (MDOT, JCK, BW)
 - N48°E 65.20' to set N & T in NW side 19" W. Pine scribed 'CCBT'
 - West 26.40' to 'I-13' - T20N, R3E - Arenac Co. Mon.
 - South 1' to set Blue Carsonite Post with Loc. Tag



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 2/7/2005