

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____
 Arenac _____ Located In _____ Corner Code # _____
 (County)

1. Public Land Survey	T	19N	R	3E	B6
	T	19N	R	3E	D6
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Oct. 27, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B6 - None

D6 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B6 - C ¼, Sec. 18 - Found ½" x 18" CIR #47943 - 50427 at calculated intersection of ¼ line per DNR info. Provided to SSI. CIR in open swampy in open swampy area E-W fence is 17' N.

D6 - C ¼, Sec. 17 - Set stamped 2" Alum. Cap on 5/8" x 4' long iron rebar per Standard BLM procedure at intersection of ¼ lines in Willow swamp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B6 - Replaced ½" CIR with stamped 2" Alum. Cap on 5/8" x 34" rebar.
 S51°E 41.36' to set ½" x 18" rebar
 N57°E 48.23' to set ½" x 18" rebar
 S64°W 41.98' to set 'T' iron, 24" long
 N51°W 50.74' to set ½" x 1.8' long pipe
 Set Blue Carsonite Post with loc. tag 1' North

D6 - Stamped 2" Alum. Cap on 5/8" x 4' long iron rebar
 N38°E 33.55' to set 24" long T-iron
 S79°E 31.16' to set ½" x 18" rebar
 S19°W 32.28' to set ½" x 18" rebar
 N17°W 30.50' to set 3/8" x 18" rebar
 Set Blue Carsonite Post 1' S.

Signed by:

Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date:

11/30/2005