

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Arenac Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 4 T 19N R 3E 3
 S 4 T 19N R 3E 5

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Oct. 27, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1					•	•							
2	6			5		4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

5 - None

3 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

5 - CN 1/16 Cor., Sec. 4 -
 Set 2" Alum. Cap (stamped) on 5/8" x 34" rebar per Standard BLM procedure.

3 - N 1/16, Cor. common to Sec. 4 & 5 -
 Set stamped 2" Alum. Cap on 5/8" x 4" Rebar per Standard BLM procedure in grassy swamp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5 - Set 2" Alum. Cap on 5/8" x 34" rebar
 S86°E 51.81' to set N & T in S. side 14" J. Pine
 S22°E 36.58' to set N & T in W. side 3" J. Pine
 S37°W 20.47' to set N & T in E. side 4" J. Pine
 S86°W 21.4' to centerline 1" Tamarack @ blaze
 Set Blue Carsonite Post with loc. tag 1' SE

3 - Set stamped 2" Alum. Cap on 5/8" x 4" rebar
 S64°E 21.13' to set 'T' iron 1' long
 S17°E 86.20' to set N & T in E. side 14" Ash
 S19°W 52.71' to set N & T in E. side 10" Ash
 S47°W 55.44' to set N & T in SE side 12" Ash
 Set Blue Carsonite Post with loc. tag 1' SW

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/30/2005