

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Arenac (County)

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 8 T 19N R 3E 11
 S 8 T 19N R 3E 12

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Sept. 26, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5			●	●									
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

11 - None

12 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

11 - SW 1/16 Cor., Sec. 8 -
 Set 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure. Fence to E. is 22'± N. Fence to S. is 55'± W. Fence curving through trees to E & S is 14'± NW.

12 - CS 1/16, Cor., Sec. 8 -
 Set 5/8" x 48" rebar with stamped 2" Alum. Cap per BLM procedure. E-W fence is 39' N. Centerline E-W ditch is 22' N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11 - Set 2" Alum. Cap on 5/8" x 34" rebar
 N20°W 5.80' to set N & T in E. side 8" Oak
 N48°E 7.95' to set N & T in SE side 6" Oak
 S02°E 11.93' to set N & T in W. side 16" Oak
 S58°W 13.04' to set N & T in SW side 7" Oak
 Set Blue Carsonite Post with loc. tag 1' NW

12 - Set 5/8" x 48" rebar with stamped 2" Alum. Cap
 N57°W 73.12' to set N & T in NE. side 9" B. Cherry
 Set Blue Carsonite Post with loc. tag 1' N
 N11°E 41.88' to set N & T in W. side 8" B. Cherry
 N47°E 55.27' to set N & T in SE side 12" Oak
 S8°W 26.21' to set 1/2" x 23" rebar

Signed by: Craig W. McVean Date: 11/30/2005

Surveyor's Michigan License No.: 39088