

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac _____ (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 14 T 19N R 3E	4
	S 14 T 19N R 3E	5
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Oct. 13, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

4 - None 5 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p><u>4</u> - NW 1/16, Sec. 14, T19N, R3E - Set Stamped 2" Alum. Cap on 5/8" x 4" iron rebar in Marsh per Standard BLM procedure. Centerline NE-SW Gravel Rd. is NW 23'±.</p>	<p><u>5</u> - CN 1/16, Sec. 14, T19N, R3E - Set stamped 2" Alum. Cap on 5/8" x 3/4" iron rebar per Standard BLM procedure. Falls in remains of N-S Fence. Apparent old fence corner remains N, S & W is 11.5'± S.</p>
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><u>4</u> - Stamped 2" Alum. Cap on 5/8" x 4" rebar Set Blue Carsonite Post w/ loc. tag 1' NW N37°W 22.91' to set 1/2" x 18" rebar in centerline NE-SW Gravel Rd. S47°W 42.14' to set N & T in SE side twin 4" & 7" Oak N54°E 24.85' to set N & T in NW side Tri. 5" W. Birch N86°E 49.91' to set N & T in N. side 10" W. Pine</p>	<p><u>5</u> - Stamped 2" Alum. Cap on 5/8" x 3/4" rebar Set Blue Carsonite Post with loc. tag 1' NW. S4°W 14.52' to set N & T in W. side 3" J. Pine S84°W 15.38' to set N & T in N. side 3" Oak N8°W 23.39' to set N & T in E. side Tri. 22" R. Maple N79°E 12.05' to set N & T in S. side 4" W. Oak</p>
---	---

Signed by: Craig W. McVean Date: 11/30/2005
 Surveyor's Michigan License No.: 39088