

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners in:
Arenac Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 15 T 19N R 3E 9
 S 15 T 19N R 3E 16

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Oct. 13, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15	●	14		13		
7								●					
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

9 - None



16 - CSR - FB #1A, p. 11 & 18 - 1911
 N86°30'W from (I-7'). 20.00 Set Post.
 Corrected post 21 1/2 E. of Lucas and 15 1/2 N.
 48 1/2 L. S. of my line to Lucas.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

9 - CE 1/16 Cor. Sec. 15
 Set Stamped 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure.
 Centerline overgrown E-W 2-track is 2.5'± S.
 Old fence cor. remains S & E is 3'± E. and 30'± S.

16 - E 1/16 Cor. common to Sec. 15 & 22
 No evidence of Co. survey post.
 Set stamped 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure.
 Centerline E-W Gravel Road is 12.5' S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

9 - Stamped 2" Alum. Cap on 5/8" x 34" rebar.
 Set Blue Carsonite Post with loc. tag 1' NW
 N64°E 27.72' to set N & T in NW side 6" Oak
 N25°W 56.44' to set N & T in NE side 3" Oak
 S46°W 34.35' to set N & T in NW side 5" Oak
 S13°W 46.19' to set N & T in W. side 5" Oak

16 - Stamped 2" Alum. Cap on 5/8" x 34" rebar - Down 0.6'.
 N23°W 57.97' to set N & T in SW side 17" R. Pine
 N57°W 81.34' to set N & T in NE side 12" R. Pine
 S33°E 58.69' to set N & T in SW side 13" W. Pine
 S4°E 51.83' to set N & T in E. side 12" W. Pine
 North 16.5' Set Blue Carsonite Post with loc. tag.

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/30/2005