

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Arenac Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T 19N R 3E C3
 T _____ R _____
 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
 3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 13, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C3 – GLO – Set Post – John Mullett – 1846
- Tamarack 10" N68°W 31 L.
- Tamarack 6" N50°E 33 L.
- CCC Notes – 1930's – Random line N, S, E & W – No corner noted.
- CPC Survey – Drawing #SF16944 – Sheet 98
- 1968 – Corner set

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C3 – Sec. Cor. common to Sections 5, 6, 7 & 8 – Fd. Consumer 'T' iron – 24" long with 3/8" x 18" long rebar alongside in swamp. No GLO evidence found. Consumer set single proportion between Sec. corner's 1 mile N & S. 'T' iron is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C3 – Replaced 'T' iron and 3/8" rebar alongside with
- 4" Stamped Aluminum DNR Cap on 1" x 5' long galv. iron pipe.
- S78°W 19.58' to set N & T in N. side 7" R. Maple scribed 'XBT'
- S56°W 12.93' to set N & T in SE side 4" Elm
- S36°E 35.31' to set N & T in SW side 6" Red Maple scribed 'XBT'
- N63°E 31.37' to set N & T in N side 7" Elm
- Set Blue Carsonite Post 1' E



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 9/22/2005

Register of Deeds Stamp & File Number

