

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arcnac (County)	Located In	Corner Code #	
1. Public Land Survey	T 19N R 3E	F5	
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5						●							
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Craig W. McVean, in a field survey on Oct. 12, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F5 - GLO - Set 1/4 Post - John Mullett - 1846
W. Pine 18" S46°E 8 L.
Hemlock 10" N84°W 20 L.
- S. J. E. Lucas - Co. Sur. - 1914
Galv. iron gas pipe 1 1/4" x 6' for corner.
- CCC - 1930's - Random @ 200 CH.
Fd. old iron post 47 1/2 W. 1 1/2 S. of random.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F5 - 1/4 Corner common to Sec. 9 & 16 - Fd. bent 1 1/4" I. D. x 5.5' long galv. iron pipe per Lucas. No GLO evidence. Lucas Map indicated pipe established 40 CH. E & W of corners at 'E5' and 'G5' on line. Bent 1 1/4" pipe accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F5 - Cut off bent top 2.8' of 1 1/4" pipe and add stamped 2" Alum. Cap on 5/8" x 4' long iron rebar into centerline of 1 1/4" x 2.7' long galv. iron pipe.
Set Blue Carsonite Post 1' N
S61°E 18.76' to set N & T in NE side 14" Oak scribed 'XBT'
N24°W 10.95' to set N & T in W. side 5" R. Maple scribed 'XBT'
N79°W 32.95' to set N & T in S. side 4" R. Maple scribed 'XBT'
S46°W 40.95' to set N & T in SE side 2" Oak



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 9/22/2005