

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac _____ (County)	Located In	Corner Code #
1. Public Land Survey	T 19N R 3E	G2
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Aug. 30, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G2 - GLO - Set 1/4 Post - J. Mullett - 1846  
 Aspen 8" N46°W 26 L.  
 Aspen 10" S65°E 13 L.  
 - MDOT - 1965 - No corner found.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

G2 - 1/4 Corner common to Sec. 3 & 4 - No GLO evidence or corner evidence found. Set 4" DNR Alum. Cap on 1" x 36" galv. iron pipe by single proportion to GLO between found MDOT positions at 'G1' and 'G3'. DNR Mon. accepted as a careful and faithful re-establishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G2 - 4" DNR Alum. Cap on 1" x 36" galv. iron pipe  
 Set Blue Carsonite Post 1' N  
 N58°E 18.89' to set N & T in N. side 8" Ash  
 S52°E 15.72' to set N & T in SW side 5" Elm  
 S14°E 38.11' to set N & T in W. side 4" R. Maple scribed 'XBT'  
 N70°W 25.91' to set N & T in N. side 4" R. Maple scribed 'XBT'

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4	●	3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 9/22/2005