

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:			
<u>Arenac</u>	Located In	Corner Code #	
(County)			
1. Public Land Survey	T <u>19N</u> R <u>3E</u>	<u>G6</u>	
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 6, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| <p><u>G6</u> – GLO – Set ¼ Post – John Mullett – 1846
 W. Pine 20" N84° 25 L.
 Sugar 10" S84° 45 L.
 - CSR – FB '1A' P. 19 – 1911 – Set Cedar post.
 Buried 2 cast iron car spring boxes and mark WP
 20" N82½°W 36
 - Co. Survey Map – S.J.E. Lucas - 1914
 This corner found 50 L too far N.
 This corner not changed.</p> | <p>- CSR – FB. 20, P. 37 – 1921 – 40.82 Ch to 'G7'.
 Old: PS 20" N82°W 36;
 New – PS 24" S71¼°W 21;
 PS 30" N9°W 74¼;
 PS 24" S15½°E 60;
 PS 24" S33°E 62
 - Unrec. Sur. – Northeast Land Surveys - #B15193 –
 Bill Woods – 1997 – Set ½" bar & cap</p> |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G6 – ¼ Cor. Common to Sec. 15 & 16 – Fd. Rotten cedar stake remnants with 2 cast iron car spring boxes on SW & SE side of stake – Down 0.7' per County Surveyor records. N82°W 36 L. find remains to ground of Pine Stp. – OBT. Stake remains with spring boxes is accepted as the best available evidence of the position of the original corner.

Reference Pt. – S8°06' E 43.79' from 'G6' find ½" capped iron #25882 – midway between 'G5' and pipe in road intersection ½ mile south. Couldn't accept this ½" capped iron over long established Co. Surveyor position. ½" CIR not utilized as 'G6' in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G6 – Drove 2" stamped Aluminum cap on 5/8" x 34" rebar into stake remains with spring boxes on SW & SE side.
 N61°E 48.08' to set N & T in SE side 7" Oak
 S73°E 81.56' to set N & T in NE side 6" Red Maple
 S30°W 26.82' to set N & T in SE side 4" Oak scribed 'XBT'
 S78°W 41.33' to set N & T in NE side 6" Oak scribed 'XBT'
 Set Blue Carsonite post 1' Southwest
 S8°06'E 43.79' to reference pt. - ½" capped iron #25882.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 9/22/2005

