

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac (County)	Located In	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>4E</u>	<u>I - 4</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Oct, 26, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-4 - GLO - Set 1/4 post - J. Burt - 1843
 S. Pine 7" S62°W 7 L.
 S. Pine 6" N32°W 24 L.
 - Rec. Sur.- L.1, Pg. 528 - D. Burgin - 1985
 Set capped 'T' iron
 S2°E 51.42' to nail in 14" Oak
 S66°E 42.65' to nail in 16" Pine
 S80°E 20.21' to nail in 10" Pine
 N30°E 6.48' to nail in 6" Pine

- LCRC - L.2, pg. 217 - K. Pomaville - 2000- found 'T' iron with cap per Burgin. Same wits. as Burgin.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

I-4 - 1/4 corner common to section 10 & 11 - found 'T' iron with cap #29240 - 18" long per record survey and LCRC.
 Burgin set midway & on line between I-3 & I-5. C/L of N-S 2- track is 21' W.
 'T' iron accepted as a careful & faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4 - Replaced 'T' iron with 4" DOC (DNR) brass cap on 1" X 3.5' iron pipe.
 Set blue carsonite post 1' E
 N29°E 6.38' to set N&T in W. side 7" J. Pine scribed 'XBT' (DB, KP)
 S85°E 20.06' to set N&T in N side 11" Jack Pine scribed 'XBT'
 S7°E 51.30' to set N&T in W side 15" Oak (DB, KP)
 N15°E 44.86' to set N&T in E side 11" Oak scribed 'XBT'
 S48°W 3.85' to set N&T in SE side 5" J. Pine scribed 'XBT'



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/13/2001