

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac _____ (County)	Located In _____	Corner Code # _____
1. Public Land Survey	T <u>19N</u> R <u>4E</u> <u>K1</u>	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

**Register of Deeds Stamp & File Number**

I, Craig W. McVean, in a field survey on October 4, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-1 -GLO - Int. N. Bdy. 46 link west of post  
 Hemlock 6" corner of section 1 & 2-J. Burt-1843
- CSR-Fb. 6, P. 34-1907. Found post in road. W. Pine st. 24" S53°W 74; SE corner log shop N6.5°W 58
  - CSR-Fb. 16, P. 25-1921- Pine st. 24" S80.5°W 60.5
  - Rifle River Valley Plat - L. 2 of Plats , p. 60-C.H. Carlson-1958.
  - LCRC - L. 1, P. 164, R.L. Higgins -1982- 1/2" bar and cap  
 Sp. in NW face of 25" W. Pine S30°W 44.68'  
 Sp. in SW face of 10" Tri. Apple NW 51.43'  
 Sp. in NE face of F.P. NE 43.05'; 'T' iron with Flint survey Co. cap -South 33.0'
  - Rec. Sur.- L.2,P. 86- T.L. Lapham -1994. Found 1/2" iron replaced with C.I.; S39°W 44.90", 34" W. Pine; South 29.46', fence corner;  
 N46°E, 43.08' fence post; N6°W, 51.17' 10" Apple (Tw.)

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

- K-1 - Closing section corner common to section 1 and 2, T19N, R4E- Found 1/2" X 18" CIR #27595 per record survey. Centerline of East-West gravel road is 2.5± North. Old fence line to south. Removed 1/2" CIR and excavated 3' X 6' area in road looking for any other evidence but found none. 1/2" CIR accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- K-1 Replaced 1/2" X 18" CIR #27595 with 3" Arenac Co. Remon. Brass cap on 5/8" X 34" rebar with tin can with concrete around cap - down 0.5'  
 South 33.33' to found 'T' iron (RLH,TLL)  
 N08°W 50.79' to found Nail in East side of 12" Tw. Apple (RLH,TLL)  
 S32°W 44.93' to found nail in NW side of 30" W. Pine (RLH,TLL)  
 S61°E 59.89' to set nail and tag in SW side of 9" Tw. W. Pine  
 East 30.13' (30.36' - GLO) to K13, T20N,R4E - Arenac Co. Mon.



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 12/13/2001