

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Arenac</u> (County)	Located In	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>4E</u>	<u>K-2</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Nov. 1, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2	●	1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-2 - GLO - Cedar 7" qr. sec. corner - J. Burt - 1843 - CSR - F.B. 1, pg. 34 - 1910- same ref. as F.B. 6, pg. 31
 Cedar 6" N88°E 3 L.
 - CSR - FB. 6, Pg. 31 - 1907
 found original wit. to corner
 Ironwood 8" S25°E 55
 Beech 11' S52 ¼ °E 35
 Hemlock 5" S59 ¼ °W 12

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

K-2 - ¼ corner common to sec. 1 & 2 - Found 'T' iron with cap # 7434 by Flint Engineering on west side of rotted off 5" X 2.5' long flat bottom wood fence corner post. Line of cedar posts to north. Remains of barb wire fence east & west. North - south fence remains on north side of Rifle river on line between 'T' iron & corner 'K1'. 'T' iron fits proportionally N & S to GLO and Co. Sur. Rec. distances.
 Accept 'T' iron at historical fence corner as a careful & faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 - Replaced 'T' iron - 18" long with 3" Arenac Co. Remon. brass cap on 5/8" x 34" rebar in ring of stone.
 Set orange carsonite post 1' North
 S54°W 15.40' to found nail in NW side 4" Fir
 N70°W 13.87' to found nail in SW side 7" W. Birch
 N58°E 3.94' to found nail in NW side 8" B. Cherry
 S19°E 35.44' set N&T in W. side 10" S. Maple
 S30°E 18.09' found nail in NE side 9" W. Birch
 N60°W 34.12' set N&T in S side 9" Ash
 SE 0.55' to fd. 'U' iron fence post



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/13/2001