

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Arenac Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T 19N R 4E K4
 T _____ R _____
 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
 3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on October 26, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K 4 – GLO – Set post – J. Burt – 1843
 W. Pine 22" N26°W 6 L.
 W. Pine 10" S26°E 9 L.
 - CSR – Lg. Bk., P. 37 – G.F. Carscallen - 1900
 Witnesses plain. Set piece of sleigh shoe iron at corner.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

K 4 – ¼ corner common to Sec. 11 & 12 - Searched for evidence of Carscallen position over wide area. Fd. old fence corner for fences E, W & N. Dug for evidence of sleigh shoe iron & GLO BT's at & around fence corner but found nothing.– Fd. 22" W. Pine Stp. remains for apparent GLO BT and set 4" DOC (DNR) alum. Cap on 1" x 4' galv. Iron pipe at record GLO bearing and distance from BT. This position is 2 foot South of a split with the overall grid distance of 5277.57' vs. 5280' – GLO for the overall mile. Corner position is 1.24 feet West of straight line from K3 to K5. Dug at SE BT's position and found some burnt pine wood. 22" WPS is only visible pine stp. in area which is low and damp. Corner of newer fences N & W is 29.5' + S & 14' E. Corner of old fences we dug at is 13'+N & 5'+E. Also dug for 16" W. Pine line tree 169.6' south. Found remains of fallen pine tree lying E-W underground 2" – burnt & rotten- at record line tree position. 4" DOC (DNR) monument accepted as a careful & faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K 4 – 4" DOC (DNR) alum. cap on 1" x 4' iron pipe with ring of stone
 East 1' to set Blue Carsonite Post.
 N10°W 22.68' to set N&T in W. side 4" Oak
 S67°E 32.36' to set N&T in SW side 12" R. Maple scribed ' XBT'
 S6°E 20.69' to set N&T in E side 5" R. Maple
 S37°W 7.90' to set N&T in SE side 6" Fir scribed ' XBT'
 N26°W 4.9' to C/L remains 22" WPS. (GLO)

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11	●	12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/13/2001