

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Lake Located In Corner Code #
 (County)

1. Public Land Survey	T	<u>19N</u>	R	<u>4E</u>	<u>K6</u>
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on October 4, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14	●	13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration

K-6 -GLO- Set 1/4 post-J. Burt- 1843.

B. Ash 10" N46°W 28 links

Elm 10" N46°W 12 links

-CSR-Fb.-8, P. 45 & 46-1909. Didn't find 1/4 post. Set Cedar post with Cedar post 50 links east and one 50 links West.

-MDOT-1957-Found 4" X 4" wood stake. Set 1 1/4" iron bar; Corner fence post S45°E 47.82'; 26" Poplar N63°E 69.25'; 6" Willow N38°W 28.73'

-LCRC-L.1, P.274- J.W. Sedgeman-1979. Found bent pipe, reset 1/2" bar - RLS capped; S70°W 19.69' - 8" Willow;

N15°W 74.26 - 20" Elm; N75°E 69.88'- 34" Cottonwood

-LCRC -L.1, P. 50-C. Kiiskila-1995. Found 1/2" rerod (used) and bent 1 1/4" pipe; 12" twin willow S86°W 22.04'; 20" Elm N14°W 74.26°; Telephone riser box N62°E 46.58°; CTR steel light pole S38°E 55.67°; CTR. N-S road East 4.5'.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

K-6-1/4 corner common to section 13 and 14 - Found 1/2" X18" rebar with bent 1 1/4" X 2.5' long rod 0.25' S. per LCRC's. Centerline of N-S gravel road is 4.5' East. MDOT appears to have found old Co. Sur. post in 1957 here. 1/2" rebar accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 -Replaced 1/2" X 18" rebar and 1 1/4" iron bar alongside with 3" Arenac County Remon. brass cap on 5/8" X 34" rebar with tin can with concrete around cap- down 0.5'

N18°W 74.21' to set nail and tag in West side of 24" Ash (JWS, CK)

N34°W 28.93' to set nail and tag in West side of 24" Willow (MDOT,CK)

S40°E 55.80' to center of 4 1/2" steel lamp post (CK)

N76°E 104.5' to center of 8" Spruce

East 26.8' to found leaning 1" iron pipe



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/13/2001