

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Arenac Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

|                                      |   |            |   |           |           |
|--------------------------------------|---|------------|---|-----------|-----------|
| 1. Public Land Survey                | T | <u>19N</u> | R | <u>4E</u> | <u>L7</u> |
|                                      | T | _____      | R | _____     | _____     |
| 2. Property Controlling in Section   | S | _____      | T | _____     | _____     |
|                                      | S | _____      | T | _____     | _____     |
| 3. Miscellaneous Property in Section | S | _____      | T | _____     | _____     |
|                                      | S | _____      | T | _____     | _____     |

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on November 14, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

L7 - GLO - Set 1/4 post - J. Burt - 1843  
 Hemlock 5" N64 1/2 E 24 1/2 L.  
 Maple 20" S83°W 19 L.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L7 - 1/4 corner common to Sec. 13 & 24 - Fd. Old wood anchor post bottom at intersection of old fences N, S, E & W. Aerial photos from 1950's show long E-W occupation line fit's this position. Old fence corner accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L7 - Set 3" Arenac Co. Remon. Brass Cap on 5/8" x 48" long rebar in remains of old rotten anchor post bottom. Set orange carsonite post 1' N.  
 S83°W 14.51' to N & T in S side 7" R. Maple scribed 'XBT'  
 N23°E 10.11 to N & T in E side 7" R. Maple scribed 'XBT'  
 S17°E 22.24' to N & T in W side 10" W. Pine  
 S85°E 59.23' to N & T in S side 8" W. Pine  
 Add ring of cobble stones.



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 12/13/2001