

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac (County)	Located In	Corner Code #
1. Public Land Survey	T 19N R 4E T 19N R 5E	M5 A5
2. Property Controlling in Section	S T R S T R	_____ _____ _____
3. Miscellaneous Property in Section	S T R S T R	_____ _____ _____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on November 8, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- M5 & A5 – GLO – Set post – L. Clason – 1837
  - Y. Pine 12" S78 ½°W 29 L.
  - W. Pine 10" N70°W 44 L.
- GLO – T19N, R5E – J. Burt – 1843
  - W. Pine 22" S80°E 48 L.
  - W. Pine 20" N29°E 14 L.
- CSR – FB. 1, P.1 – WPS 18" N 43 ½° E 55 – 1910
- MDOT Notes – 1957 – Dug hole 10' x 6' x 2'
- Set 1 ½" x 1 ½" steel fence post by single proportion.
- 6" W. Birch S42°W 76.90'; 4" Oak N64°W 59.00';
- 10" Oak S63°E 66.30

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

M5 & A5 – Standard Section corner common to Sec. 12 & 13, T19N, R4E & Sec. 7 & 18, T19N, R5E – Fd. 1 1/2" iron fence post per MDOT. All pine stp. evidence in area is gone. Corner of single strand wire & post to N & W is 3' N & 13.5' E. MDOT set 1 ½" fence post by single proportion between M3 - A3 and M7-A7. 1 ½" iron fence post accepted as a careful & faithful re-establishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M5 & A5 – Replaced 1 1/2" x 24" iron fence post w/ 4" DNR alum. cap on 1" x 36" galv. iron pipe. Set Blue Carsonite Post 1' SE. N63°W 58.54' to set N & T in SW side 14" Oak scribed 'XBT' (MDOT)  
 N28°E 45.93' to set N & T in W side 4" Oak scribed 'XBT'  
 S87°E 19.72' to set N & T in N side 6" R. Maple scribed 'XBT'  
 S30°E 6.89' to set N & T in SW side 6" Oak scribed 'XBT'



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 12/13/2001