

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Arenac Located In _____ Corner Code # _____
 (County)

1. Public Land Survey	T	<u>19N</u>	R	<u>4E</u>	<u>M6</u>
	T	<u>19N</u>	R	<u>5E</u>	<u>A6</u>
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on December 5, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M6 & A6 – GLO – Set ¼ post – L. Clason – 1837
 Y. Pine 12" S49°W 21 L.
 Hem. 12" N15°W 12 L.
 - CSR – FB. 6, P.10 – 1905 - M6 to M7 – 39.84CH
 - MDOT – 1957 – Dughole 10' x 6' x 2' – set
 1" angle iron by single prop. measurement
 9" Maple N51°W 47.60'; 6" Maple N46°E 86.80';
 7" Maple S71°E 80.14'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

M6 & A6 – Standard ¼ corner common to Sec. 13, T19N, R4E & Sec. 18, T19N, R5E – Fd. 1" x 1" x 24" long 'L' angle iron per MDOT. Old Down N-S barb wire fence is 31' + E. Measure Grid Dist. S. 2634.66' (2629.44' CSR, 2635.15' MDOT) to M7-A7. N33°48'W 19.53' to found ½" iron bolt w/ 1 1/8" head in old excavation pit. Appears this bolt was set in the center of MDOT excavated hole. Some newer wood posts run N & S of the bolt. No GLO evidence to support bolt. Bolt rejected. 1" angle iron accepted as a careful & faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M6 & A6 – Replaced 1" x 1" x 2.4' angle iron w/ 4" DNR alum. Cap on 1" x 36" galv. iron pipe. Set Blue Carsonite Post 1' W. N50°W 47.65' to set N & T in SW side 15" R. Maple scribed 'XBT' (MDOT)
 S68°E 79.90' to set N & T in NE side 16" R. Maple (MDOT)
 N7°W 31.93' to set N & T in E side 3" W. Pine
 S49°W 26.61' to set N & T in SE side 9" Oak scribed 'XBT'
 N33°48'W 19.53 to ½" iron bolt w/ 1 1/8" head.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/13/2001