

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac (County)	Located In	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>4E</u>	<u>I-1</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on January 3, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-1 - GLO - Int. N. Bdy. 68 links west of post. Set post corner of section 2 & 3 - J. Burt - 1843.
 Aspen 10" S40°W 19 links
 - CSR - FB. 6, P. 30-36 - 1907 - Sec. 2 & 35 Surveys
 Pine stump 24" S12.5°W 88.5
 East 60 links stream 5 links Co. S.
 - LCRC - L. 1, P. 164- R.L. Higgins - 1982
 Found concrete monument - PK in blaze 13" Cedar N23°W 18.61'; Found 9" Birch with blaze set 6' above Grd. in SE face N25°E 26.94'; Found PK in blaze 5" Cedar S15°E 12.58'; Found 1/2" bar East 44.01' the SW corner section 35, T20N, R4E.

-Recorded survey - L.2, P. 230 - J.H. Granger - Found 2" pipe - 1998
 -LCRC - L.2, P.226 - K.T. Pomaville - 2000. Found concrete monument on steep bank. Appears to be disturbed and doesn't fit record witnesses. Set 1/2" rod with cap per Higgins witnesses. N26°W 19.14' to found nail in SW/S 13" Cedar; N26°W 18.62' to found PK in blaze in face of 13" Cedar (18.61'-R); N24°E 29.94' to found nail in SE/S 9" Birch (26.94'-R); East 44.01' to found 1/2" rod; S23°E 11.89' to found PK in blaze face of 5" Cedar (12.58'-R); S23°E 12.50' to set nail in E/S 5" Cedar; S51°E 16.26' to set nail in SE/S 6" Cedar; S66°W 3' to found concrete monument (disturbed).

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

I-1 - Closing Sec. corner common to Sec. 2 & 3, T19N, R4E - Could find no evidence of Pine St. BT per CSR. Area of stp. disturbed. Set 3" Arenac Co. Remon. Brass Cap on 5/8" x 4' Rebar at GLO record distance west of I-13, T19N, R4E on standard line as defined by fence & irons in this area and irons found 33' north of platted 'Fritz Road' - 1/2 mile to west. West bank of stream 20'+ wide is 39' E (39.6' - CSR notes). Corner I-13, T20N, R4E is in stream as noted by Arenac Co. Sur. notes. Arenac Co. Mon. accepted as a careful & faithful re-establishment of the position of the original corner.

Reference Pt. - Fd. 1/2" CIR #43066 per Pomaville LCRC is N89°51'W 24.14' from 'I-1'. Could not accept 1/2" CIR 43066 since it doesn't fit Arenac Co. Sur. notes topographic call to edge of stream. Stream in 'V' canyon and hasn't moved. 1/2" CIR #43066 not utilized as 'I-1' in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 - 3" Arenac Co. Remon. Brass Cap on 5/8" x 4' Rebar in ring of stones.
 South 1' to set orange carsonite post
 S42°E 7.00' to N & T in W side 7" Cedar
 N56°W 30.62' to N & T in E side 13" Cedar
 N89°51'W 24.14' to 1/2" CIR #43066 - Ref. Pt.
 N89°55'46"E 19.71' to Fd. 1/2" iron rod
 N89°55'46"E 44.88' (GLO & M) to I-13 - T20N, R4E - ACM



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 1/14/2002