

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:			
<u>Arenac</u>	Located In	Corner Code #	
(County)			
1. Public Land Survey	T <u>19N</u> R <u>4E</u>	<u>L4</u>	
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Craig W. McVean, in a field survey on January 8, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L4 – CSR – Lg. Bk. P. 37 – G.F. Carscallen – 1900
Set Temp Center post in swamp.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L4 – C ¼, Sec. 12, T19N, R4E – No evidence of Carscallen Temp. Center post found. Set 3 ½" DNR Alum. Cap on 1" x 35" Galv. Iron pipe at intersection of ¼ lines per standard BLM procedure in swamp. Corner of single strand wire E & S is N86°E 82'. DNR Mon. accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L4 – 3 ½" DNR Alum. Cap on 1" x 35" long galv. Iron pipe
NW 1' to set Blue Carsonite Post with location tag
N42°W 7.29' to N & T in SW side 4" R. Maple scribed 'XBT'
S34°W 22.52' to N & T in SE side 5" W. Oak scribed 'XBT'
S82°W 37.39' to N & T in S side 7" Spruce scribed 'XBT'
N85°E 67.73' to N & T in S side 15" Tw. R. Maple



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 1/19/2002