

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:			
Arenac	Located In	Corner Code #	
(County)			
1. Public Land Survey	T <u>19N</u> R <u>4E</u>	<u>L5</u>	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on January 3, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5											●		
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- L5 – GLO – Set ¼ post – J. Burt – 1843
 Elm 18" S25°E 52 L.
 - CSR – Lg. Bk., P. 37 – 1900
 Post – G.F. Carscallen
 - Rec. Sur. – L. 2, P. 150 – J.F. Oliver – 1996
 Fd. 1" Pipe

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L5 – ¼ corner common to Sec. 12 & 13 – Could find no conclusive evidence of corner. Set 4" DNR Alum. Cap on 1" iron pipe by single proportion between K5 and M5. Measured North 5286.93' vs. 5280' – GFC to 'L3' and West 2668.54' vs. 2656.5' – GFC to 'K5'. East 28' to W. bank 5'+ wide creek. West 29' to N-S single strand barb wire. DNR Mon. accepted as a careful & faithful re-establishment of the position of the original corner.

Reference Pt. - S34°01'W 53.56' from 'L5' to calculated position for 1" pipe noted by J.F. Oliver per record survey L. 2, P. 150. Didn't find pipe though this position is on NE side of Cedar anchor post for single strand wires to N, S, E & W. This position was apparently established by projecting the center line of road West of 'K5' easterly at record GLO distance of 2637.36' east of 'K5'. Didn't accept this calculated position since it would place large deflection in Sec. line and cause shortage into N-S ¼ line to S. & over run to North that would be inconsistent with Carscallen's 1900 survey. Distance West to K5 would also be short of Carscallen. Oliver position not utilized as 'L5' in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L5 – 4" DNR Alum Cap on 1" x 5' long galv. Iron pipe
 NW 1' to set Blue Carsonite Post
 S35°W 55.05' to N & T in NW side 8" Cedar fence post
 N38°W 14.24' to N & T in NE side 8" R. Maple scribed 'NBT'
 N4°E 27.26' to N & T in W side 10" R. Maple scribed 'XBT'
 S62°W 47.20' to N & T in SE side 7" Cedar
 South 25.57' to N & T in E side 6" Ash



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 1/14/2002