

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac (County)	Located In	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>4E</u> L6	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on January 8, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L6 - None

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L6 - C ¼, Sec. 13, T19N, R4E - Set 2" Alum. Cap on 5/8" x 34" Rebar at intersection of ¼ lines per standard BLM procedure.  
N-S single strand of smooth wire is 13.5' W. 2" AC accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L6 - 2" Alum Cap on 5/8" x 34" Rebar.  
E 1' to set Blue Carsonite Post with location tag.  
S62°W 17.98' to N & T in N side 9" Oak scribed 'XBT'  
S11°E 25.29' to N & T in E side 8" Oak scribed 'XBT'  
N14°W 15.61' to N & T in W side 16" Oak scribed 'XBT'  
N50°E 20.48' to N & T in E side Tw. 9" Oak scribed 'XBT'

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 1/14/2002