

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Arenac \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey		T _____	R _____		
		T _____	R _____		
2. Property Controlling in Section	S <u>1</u>	T <u>19N</u>	R <u>4E</u>		<u>7</u>
	S <u>3</u>	T <u>19N</u>	R <u>4E</u>		<u>14</u>
3. Miscellaneous Property in Section	S _____	T _____	R _____		
	S _____	T _____	R _____		

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on December 4, 2001 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11				
5													
6	18		17		16		15		14				
7													
8	19		20		21		22		23				
9													
10	30		29		28		27		26				
11													
12	31		32		33		34		35				
13													

A. Description of original monument and accessories and/or subsequent restoration:

7 - None

14 - Rec. Sur. - L. 1, P. 341 - E. Goss - 1977;  
L. 1, P. 497 - L.D. McGinnis - 1983  
Both Surveys show calculated position of corner.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

7 - N 1/16 corner common to Sec. 1, T19N, R4E & Sec. 6, T19N, R5E - Set 2" Alum. Cap on 5/8" X 34" rebar per standard BLM procedure.

14 - S 1/16 Cor. common to Sec. 2 & 3, T19N, R4E - Fd. 3/8" x 18" Rebar w/ cap #18999 within 0.52' of calculated position on N. slope of hill. N-S cable is 2.5' E. Accepted 3/8" CIR as the best available evidence of the position of the corner.

Ref. Pt. - Fd. 1/2" CIR #27595 at corner of new barb wire & steel post W & N at S23°27'W 4.61' of Cor. '7'. This 1/2" CIR appears to be based on SP position for M2 which is incorrect. 1/2" CIR #27595 not utilized as cor. '7' in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

7 - 2" AC on 5/8" X 34" Rebar  
NE 1' to set Blue Carsonite Post with location tag  
S45°E 73' to NW bank of river  
N8°E 29.20' to N&T in W side 13" Ash  
S84°E 15.16' to N&T in N side 13" Ash  
S42°E 23.12' to N&T in SW side 7" Ash  
S64°W 27.31' to N & T in NW side 10" Basswood  
S23°27'W 4.61' to 1/2" CIR 27595 - Ref. Pt.

14 - Replaced 3/8" x 18" CIR with 2" Alum. Cap on 5/8" x 34" Rebar.  
SW 1' to set Blue Carsonite post with location tag.  
S20°E 6.33' to N&T in W side 11" Oak  
S28°W 11.71' to N&T in W side 3" R. Maple scribed 'XBT'  
N2°W 12.12' to N&T in E side 4" R. Maple scribed 'XBT'  
N54°W 19.74' to N&T in SW side 20" R. Pine

Signed by: Craig W. McVean  
Surveyor's Michigan License No.: 39088

Date: 3/4/2002

