

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey		T _____		R _____				
		T _____		R _____				
2. Property Controlling in Section	S <u>1</u>	T <u>19N</u>	R <u>4E</u>	<u>12</u>				
	S <u>1</u>	T <u>19N</u>	R <u>4E</u>	<u>14</u>				
3. Miscellaneous Property in Section	S _____	T _____	R _____					
	S _____	T _____	R _____					

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on April 19, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2			1	
3													
4	7		8		9		10		11			12	
5													
6	18		17		16		15		14			13	
7													
8	19		20		21		22		23			24	
9													
10	30		29		28		27		26			25	
11													
12	31		32		33		34		35			36	
13													

A. Description of original monument and accessories established and/or subsequent restoration:

12 - None



14 - CSR- F.B. 1B, Pg. 78 - 1901- Sec. 6- set post  
 - MDOT - 1957 - Fd. 4" x 4" wood stake

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

12 - CS 1/16 Cor., Sec. 1 - set  
 2" Alum. Cap on 5/8" X 34" rebar  
 per standard BLM procedure.  
 Traces of old N-S fence & field row is 2' +/- W.  
 Meandering N-S cable is 4' E

14 - S 1/16 Cor. common to sec. 1, T19N, R4E &  
 Sec. 6, T19N, R5E - Fd. 0.2' X 0.2' X 2' long Cedar stake  
 bottom with axed point in Cedar swamp per MDOT notes.  
 distance is 1314.95' vs. 1320' - CSR to M3-A3.  
 Cedar stake accepted as the best available evidence of the  
 position of the corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

12 - 2" AC on 5/8" X 34" Rebar  
 Set blue Carsonite post w/Loc. tag 1' SE.  
 N74°W 21.98' to set N&T in N side 3" Oak  
 N61°E 23.33' to SET N&T NW side 20" Oak  
 S36°E 32.25' to set N&T in SW side 20" Oak  
 S18°W 73.88' to set N&T in E side 7" J. Pine

14 - Replaced Cedar Stake w/ 2" Alum. cap on 5/8" X 5' Rebar.  
 Reset Cedar stake on S. side as memorial.  
 Set Blue Carsonite post 1' SW  
 S4°E 9.22' to N&T in E side 10" Cedar  
 S44°E 8.35' to N&T in NE side 7" Cedar  
 N58°E 14.66' to N&T in NW side 12" R. Maple  
 N30°W 25.70' to N&T in SW side 5" R. Maple

Signed by: Craig W. McVean Date: 3/4/2002  
 Surveyor's Michigan License No.: 39088