

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Arenac Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S 11 T 19N R 4E 8  
 S 11 T 19N R 4E 11

3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on November 1, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

8 - None

11 - None



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

8 - CW 1/16 cor., Sec. 11  
 Set 2" Alum. cap on 5/8" X 34" rebar  
 per standard BLM procedure.

11 - SW 1/16 Cor., Sec.11  
 Set 2" Alum. cap on 5/8" X 34" rebar  
 per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8 - 2" AC on 5/8" X 34" rebar  
 S22°W 27.28' to N&T in W. side 15" B. Oak  
 S82°W 18.28' to N&T in N. side 14" B. Oak.  
 N42°E 11.39' to N&T in E side 12" B. Oak  
 S81°E 33.67' to N&T in N side 13" B. Oak  
 Set Blue Carsonite post w/loc. tag 1' NW  
 N89°53' 59"E 218.27' to 2" AC on E. ROW of Grove Rd.

11 - 2" AC on 5/8" X 34" rebar  
 Set blue Carsonite post w/loc. tag 1' SW  
 N52°W 102.27' to N&T in NE. side 5" B. Oak  
 S69°W 49.84' to N&T in S side 21" B. Oak  
 S39°E 72.41' to N&T in SW side 25" B. Oak  
 S16°W 73.73' to N&T in E side 17" B. Oak  
 N89°57' 03"E 246.70' to 2" AC on E. ROW of Grove Rd.

Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 3/4/2002