

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Arenac Located In _____ Corner Code # _____
(County)

1. Public Land Survey T _____ R _____
T _____ R _____

2. Property Controlling in Section S 11 T 19N R 4E 9
S 11 T 19N R 4E 12

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on November 1, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

9 - None 12 - None



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

9 - CE 1/16 cor., Sec. 11
Set 2" Alum. cap on 5/8" X 34" rebar per standard BLM procedure.
E-W single strand wire is 40' +/- S.

12 - CS 1/16 Cor., Sec. 11
Set 2" Alum. cap on 5/8" X 34" rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

9 - 2" AC on 5/8" X 34" rebar
S7°W 18.58' to N&T in W. side 4" W. Pine
S80°W 56.72' to N&T in N. side 5" W. Pine
N14°W 6.54' to N&T in W side 8" W. Oak
N70°E 6.14' to N&T in N side Tw. 6" W. Oak
SW 1' to Set Blue Carsonite post w/loc. tag.

12 - 2" AC on 5/8" X 34" rebar
SE 1' to set blue Carsonite post w/loc. tag
S30°E 7.32' to N&T in W. side 7" Oak
S69°W 10.09' to N&T in SW side 6" J.Pine
N50°W 13.36' to N&T in SW side 6" J.Pine
N30°E 29.30' to N&T in SE side 15" W.Pine

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 3/4/2002